


AD-A099 089

GAI CONSULTANTS INC. MONROEVILLE PA  
NATIONAL DAM INSPECTION PROGRAM. BEAVER POND DAM (NDI I.D. NUMB--ETC(U)  
MAR 81 B M MIHALCIN

F/6 13/13  
DACP31-81-C-0015  
NL

UNCLASSIFIED

1  
AP  
AD-99089



AD A090989

LEVEL

DELAWARE RIVER BASIN  
DINGMANS CREEK, PIKE COUNTY

11  
57  
C  
C  
PENNNSYLVANIA

BEAVER POND DAM

NDI I.D. NO. PA-00408  
PENNDER I.D. NO. 52-13


DTIC  
MAY 18 1981

ECKMAN LUMBER COMPANY

PHASE I INSPECTION REPORT

NATIONAL DAM INSPECTION PROGRAM.

Beaver Pond Dam (NDI I.D. NO. PA-00408  
Penn. DEP I.D. Number - 52-13) Delaware River  
Basin, Dingmans Creek, Pike  
County, Pennsylvania  
Phase I



PREPARED FOR

M. M. M.

DEPARTMENT OF THE ARMY

Baltimore District, Corps of Engineers

Baltimore, Maryland 21203


F. D. C. W. E. L. - 411-  
PREPARED BY

12/101  
GAI CONSULTANTS, INC.

570 BEATTY ROAD

MONROEVILLE, PENNSYLVANIA 15146

11) MAR 18 1981



Original content color  
plates: All DTIC reproductions will be in black and white.

815 18038 1110

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the Spillway Design Flood is based on the estimated Probable Maximum Flood (greatest reasonably possible storm runoff) for the region, or fractions thereof. The Spillway Design Flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition, and the downstream damage potential.

Breach analyses are performed, when necessary, to provide data to assess the potential for downstream damage and possible loss of life. The results are based on specific theoretical scenarios peculiar to the analysis of a particular dam and are not applicable to other related studies such as those conducted under the Federal Flood Insurance Program.

DTIC

DISTRIBUTION STATEMENT A	
Approved for public release;	
Distribution Unlimited	

Accession for  
NTIS G-441  
DTIC T-5  
Unannounced  
Justification  
form for file.  
By \_\_\_\_\_  
Distribution/  
Availability \_\_\_\_\_  
Date \_\_\_\_\_  
A

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

ABSTRACT

Beaver Pond Dam: NDI I. D. No. PA-00408

Owner: Eckman Lumber Company  
State Located: Pennsylvania (PennDER I.D. No. 52-13)  
County Located: Pike  
Stream: Dingmans Creek  
Inspection Date: 13 November 1980  
Inspection Team: GAI Consultants, Inc.  
570 Beatty Road  
Monroeville, Pennsylvania 15146

Based on a visual inspection, operational history, and hydrologic/hydraulic analysis, the dam is considered to be in good condition.

The size classification of the facility is small and the hazard classification is considered to be high. In accordance with the recommended guidelines, the Spillway Design Flood (SDF) ranges between the 1/2 PMF (Probable Maximum Flood) and the PMF. Since the facility is classified near the lower bounds of the small category, the SDF is considered to be the 1/2 PMF. Results of hydrologic and hydraulic analyses indicate the facility will pass and/or store approximately 40 percent of the PMF prior to embankment overtopping at the low area in the embankment crest (elevation 1177.4). Breach analysis indicates that failure under less than 1/2 PMF conditions could lead to increased downstream damage and potential for loss of life. Thus, based on screening criteria provided by the recommended guidelines, the spillway is considered to be seriously inadequate and the facility unsafe, non-emergency.

It is recommended that the owner immediately:

- a. Develop a formal emergency warning system to notify downstream residents should hazardous embankment conditions develop. Included in the plan should be provisions for around-the-clock surveillance of the facility during periods of unusually heavy precipitation.
- b. Retain the services of a registered professional engineer experienced in the hydraulics and hydrology of dams to more accurately assess the adequacy of the spillway and prepare recommendations for remedial measures deemed necessary to make the facility hydraulically adequate.

## Beaver Pond Dam: NDI I.D. No. PA-00408

c. Have the embankment and adjacent abutment areas accurately surveyed and infill any low areas to restore the crest to the design elevation of 1177.5 feet.

d. Repair all areas of deterioration in the concrete surfaces of the spillway and spillway apron, and rearrange any displaced riprap in the discharge channel.


e. Remove the potentially obstructing debris lodged in the spillway forebay.

f. Remove all the trees, their root systems, and brush from the crest, upstream and downstream embankment slopes. This operation should be conducted under the guidance of a soils engineer experienced in the design and construction of earth dams.

g. Develop formal manuals of operation and maintenance to ensure the future proper care of the facility.

GAI Consultants, Inc.

Bernard M. Mihalcin  
Bernard M. Mihalcin, P.E.



Approved by:

James W. Peck

JAMES W. PECK  
Colonel, Corps of Engineers  
District Engineer

Date 30 March 1981

Date 15 APR 81



OVERVIEW PHOTOGRAPH

## TABLE OF CONTENTS

	<u>Page</u>
PREFACE. . . . .	i
ABSTRACT . . . . .	ii
OVERVIEW PHOTOGRAPH. . . . .	iv
TABLE OF CONTENTS. . . . .	v
SECTION 1 - GENERAL INFORMATION. . . . .	1
1.0 Authority. . . . .	1
1.1 Purpose. . . . .	1
1.2 Description of Project . . . . .	1
1.3 Pertinent Data . . . . .	2
SECTION 2 - ENGINEERING DATA . . . . .	5
2.1 Design . . . . .	5
2.2 Construction Records . . . . .	6
2.3 Operational Records. . . . .	6
2.4 Other Investigations . . . . .	6
2.5 Evaluation . . . . .	6
SECTION 3 - VISUAL INSPECTION. . . . .	7
3.1 Observations . . . . .	7
3.2 Evaluation . . . . .	8
SECTION 4 - OPERATIONAL PROCEDURES . . . . .	9
4.1 Normal Operating Procedure . . . . .	9
4.2 Maintenance of Dam . . . . .	9
4.3 Maintenance of Operating Facilities. . . . .	9
4.4 Warning System . . . . .	9
4.5 Evaluation . . . . .	9
SECTION 5 - HYDROLOGIC/HYDRAULIC EVALUATION. . . . .	10
5.1 Design Data. . . . .	10
5.2 Experience Data. . . . .	10
5.3 Visual Observations. . . . .	10
5.4 Method of Analysis . . . . .	10
5.5 Summary of Analysis. . . . .	10
5.6 Spillway Adequacy. . . . .	13
SECTION 6 - EVALUATION OF STRUCTURAL INTEGRITY . . . . .	14
6.1 Visual Observations. . . . .	14
6.2 Design and Construction Techniques . . . . .	14
6.3 Past Performance . . . . .	14
6.4 Seismic Stability . . . . .	15
SECTION 7 - ASSESSMENT AND RECOMMENDATIONS FOR REMEDIAL MEASURES. . . . .	16
7.1 Dam Assessment . . . . .	16
7.2 Recommendations/Remedial Measures. . . . .	16

TABLE OF CONTENTS

- APPENDIX A - VISUAL INSPECTION CHECKLIST AND FIELD SKETCHES**
- APPENDIX B - ENGINEERING DATA CHECKLIST**
- APPENDIX C - PHOTOGRAPHS**
- APPENDIX D - HYDROLOGIC AND HYDRAULIC ANALYSES**
- APPENDIX E - FIGURES**
- APPENDIX F - GEOLOGY**

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM  
BEAVER POND DAM  
NDI # PA-00408, PENNDEP # 52-13

SECTION I  
GENERAL INFORMATION

1.0 Authority.

The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

1.1 Purpose.

The purpose is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project.

a. Dam and Appurtenances. Beaver Pond Dam is an earth embankment approximately 14 feet high and 395 feet long, including spillway. The facility is provided with an uncontrolled, rectangular shaped, concrete chute channel spillway located at the right abutment. The spillway is equipped with an ogee-type weir, 110 feet in length. The outlet works consist of a 36-inch diameter reinforced concrete pipe that discharges at the downstream embankment toe near the left sidewall of the spillway. Flow through the pipe is manually controlled by a 36-inch diameter sluice gate located at the inlet.

b. Location. Beaver Pond Dam is located on Dingmans Creek in Delaware Township, Pike County, Pennsylvania. The facility is located approximately two miles east of the community of Edgemere, Pennsylvania, and less than three miles northwest of the town of Holy Trinity (off Legislative Route 51006). The dam reservoir and watershed are contained within the Edgemere and Lake Maskenoza, Pennsylvania-New Jersey, 7.5 minute U.S.G.S. topographic quadrangles (see Figure 1, Appendix E). The coordinates of the dam are N41° 15.1' and W74° 56.9'.

c. Size Classification. Small (14 feet high, approximately 150 acre-feet storage capacity at the top of dam).

d. Hazard Classification. High (see Section 3.1.e).

e. Ownership. Eckman Lumber Company  
R. D. #3  
Lehighton, Pennsylvania 18235

Attention: John Eckman, President

f. Purpose. Recreation.

g. Historical Data. Detailed correspondence from PennDER files indicate that Beaver Pond Dam was originally constructed prior to 1913 and was used for water power. The original dam was an earth and rock structure 10 feet high and only 70 feet long. By 1950, remedial measures to control seepage and correct damage from overtopping had resulted in a facility with a concrete spillway and an embankment length of about 200 feet. During the flood of August 1955, however, the dam was once again severely damaged and it was decided by the owner to reconstruct the entire facility.

In 1955, Edward C. Hess Associates, Inc., civil engineers of Stroudsburg, Pennsylvania, designed the present facility. The new dam was designed as a 350-foot long earth embankment (field measured at 395 feet) with a 110-foot concrete spillway. This facility was completed in 1956-1957 and has since functioned without any significant problems.

1.3 Pertinent Data.

a. Drainage Area (square miles). 7.0

b. Discharge at Dam Site

Discharge Capacity of Outlet Conduit - Discharge curves are not available.

Discharge Capacity of Spillway at Maximum Pool  $\approx$  5100 cfs (see Appendix D, Sheet 10).

c. Elevations (feet above mean sea Level). The following elevations were obtained from available drawings and through field measurements based on the elevation of normal pool at approximately 1172.0 feet as indicated in Figure 1 (see Appendix D, Sheet 1).

Top of Dam	1177.5 (design). 1177.4 (field).
Maximum Design Pool	Not known.
Maximum Pool of Record	Not known.
Normal Pool	1172.0 (assumed datum).
Spillway Crest	1172.0.
Upstream Inlet Invert	1165.0 (design).
Downstream Outlet Invert	1164.6 (design).
Downstream Outlet Invert	1163.1 (field).
Streambed at Dam Centerline	1164.6 (estimated).
Maximum Tailwater	Not known.

d. Reservoir Length (feet).

Top of Dam	2650
Normal Pool	2500

e. Storage (acre-feet).

Top of Dam	150
Normal Pool	61

f. Reservoir Surface (acres).

Top of Dam	20
Normal Pool	13

g. Dam.

Type	Earth.
------	--------

Length	285 feet (excluding spillway).
--------	--------------------------------

Height	14 feet (field measured; embankment crest to downstream embankment toe).
--------	--

Top Width	Varies; two feet minimum at left abutment to 10 feet maximum near spillway.
-----------	---

Upstream Slope	2H:1V.
----------------	--------

Downstream Slope	Varies; 6.5H:1V minimum to 3H:1V maximum.
------------------	---

Zoning	Homogeneous earth embankment with a rock covered upstream slope (see Figure 3).
--------	---

Impervious Core	Homogeneous earth section.
-----------------	----------------------------

Cutoff	Impervious cutoff as shown in Figure 3.
--------	---

Grout Curtain	Not known.
---------------	------------

h. Diversion Canal and Regulating Tunnels.

	None.
--	-------

i. Outlet Works.

Type	Concrete intake tower with Rodney Hunt Series 208 rising stem operator and 36-inch diameter sluice gate.
------	--

Outlet Conduit	36-inch diameter reinforced concrete pipe encased in concrete.
Conduit Length	55 feet, sluice gate to outlet endwall.
j. <u>Spillway.</u>	
Type	Uncontrolled, rectangular shaped, concrete chute channel with an ogee-type weir.
Crest Elevation	1172.0 feet.
Crest Length	110 feet.
Closure and Regulating Facilities	Manually controlled upstream of embankment centerline via 36-inch diameter sluice gate located at the inlet. The gate is housed at the base of a reinforced concrete riser situated along the upstream embankment toe.
Access	The riser is not accessible by foot from the embankment crest.

## SECTION 2

### ENGINEERING DATA

#### 2.1 Design.

a. Design Data Availability and Sources. No formal design reports or calculations are available. No information pertaining to the design of the original dam is available in the PennDER files; but, information about the present facility is contained in the above files in the form of two drawings, dated 1955 (see Figures 2 and 3, Appendix E). In addition, these files contain the state construction permit application reports, dated 1955 and 1956, which contain brief descriptions of the design aspects of the present facility.

#### b. Design Features.

1. Embankment. Details of the basic embankment design are presented in Figures 2 and 3. As indicated, the present facility was constructed atop the existing earth embankment (see Figure 3, Section E-E). Specific design features are obscure since much of the embankment, as viewed by the inspection team, differed somewhat, in dimension and cross-section from that shown in Figure 3. The renovated embankment constructed in 1956, was designed with 2H:1V upstream and downstream slopes and an eight-foot minimum embankment crest width. The embankment crest, observed by the inspection team, varied in width from ten feet near the left spillway sidewall to two feet near the left abutment. The downstream face has an irregular slope varying from 6.5H:1V to 3H:1V. The steepest downstream embankment slope coincides with the broadest section of the embankment crest near the left sidewall of the spillway. An impervious clay cutoff is apparent in the available drawings and is discussed in the state permit reports.

#### 2. Appurtenant Structures.

a) Spillway. Design features of the spillway are presented in Figures 2 and 3. As indicated, the spillway is an uncontrolled, rectangular shaped, concrete chute channel with an ogee-type weir located at the right abutment. The length of the spillway crest is 110 feet. The structure is tied into the embankment on both sides with 18-inch thick concrete key walls that are reportedly carried to impervious foundation material. The spillway was designed to discharge over a 12-inch thick grouted stone apron. At the end of the apron, an 18-inch thick curtain wall is carried down to a suitable impervious foundation material. The discharge channel downstream of the curtain wall was to be protected with randomly dumped stone.

b) Outlet Conduit. Design features of the outlet conduit are presented in Figure 3. As indicated, the outlet conduit is a 36-inch diameter reinforced concrete pipe with the inlet

located at the base of the reinforced concrete riser and the outlet at the downstream toe of the embankment immediately adjacent the left sidewall of the spillway. The concrete riser is situated on the upstream side of the embankment adjacent to the spillway. Flow through the outlet is controlled by means of a 36-inch diameter sluice gate located at the inlet. The gate is manually operated from atop the riser structure.

c. Specific Design Data and Criteria. Available design data is limited primarily to the information contained in the 1955 and 1956 state permit application reports and provided in Figures 2 and 3. No information relative to specific design procedures or applied construction techniques was obtained.

#### 2.2 Construction Records.

No formal construction records are available for the original facility built prior to 1913, or for the present facility built in 1956-1957. PennDER files contain photographs and correspondence accumulated during the years of construction; however, there is no information pertaining to specific construction aspects or techniques such as compaction procedures.

#### 2.3 Operational Records.

No records of the day-to-day operation of this facility are available.

#### 2.4 Other Investigations

Formal state inspection reports for both the original and the present facilities are contained in PennDER files for the years 1919, 1950, 1960, and 1965.

#### 2.5 Evaluation.

The available data, coupled with the information obtained during the visual inspection, are considered adequate to make a reasonable Phase I assessment of the facility.

SECTION 3  
VISUAL INSPECTION

3.1 Observations.

a. General. The general appearance of the facility suggests it to be in good condition.

b. Embankment. Observations made during the visual inspection indicate the embankment is in good condition. No seepage through the downstream face of the dam or indications of embankment instability were noted during the field inspection. Some minor deficiencies were observed which will require the remedial attention. These include:

1. Low area in the right abutment (1.1-foot below the design top of the dam) beyond the apparent end of the embankment.

2. Low area in the left abutment (0.4-foot).

3. The entire upstream embankment face is heavily overgrown with weeds, brush, and trees up to six inches in diameter.

4. The downstream embankment face in the vicinity of the spillway is covered with brush and small trees.

c. Appurtenant Structures.

1. Spillway. The condition of the spillway is considered to be good (see Photographs 8, 9, and 11). A large stump and a section of a boat dock were observed lodged in the spillway forebay. Moderate scaling and a few minor spalls were observed over the ogee crest. The spillway sidewalls exhibit only minor cracking. An apron is constructed downstream of the spillway with an approximate 15 percent grade. The apron shows signs of distress and requires remedial attention to protect it from further deterioration (see Photograph 11). Water action has displaced some of the random rock dumped adjacent to the curtain wall.

2. Outlet Works. The visible parts of the outlet works (intake structure and discharge structure) were found to be in good condition. The concrete intake structure is located approximately 25 feet upstream of the crest of the dam and was inaccessible by foot at the time of inspection (see Photographs 5 and 6). The control valve mechanism was not operated during the inspection; however, the owner stated that the gate was operated about two years ago.

d. Reservoir Area. The general area surrounding the reservoir is comprised of moderate to steep slopes that are heavily forested (see Photographs 1 and 2). No signs of slope distress were observed.

e. Downstream Channel. The spillway discharges into Dingmans Creek, a steeply sloped braided stream set in a narrow valley between steep, heavily wooded side slopes. The potential hazard area is located approximately 500 feet downstream of the dam where Dingmans Creek parallels Legislative Route 51006. Several small business establishments are located along the left bank of the stream. Many residences are located along both banks of Dingmans Creek for the next mile. Due to their close proximity to the streambed, approximately 15 homes and as many as 50 persons could be affected in this area by the floodwaters associated with an embankment breach. Consequently, the hazard classification is considered to be high.

### 3.2 Evaluation.

The overall condition of the facility is considered to be good. Low areas were noted at or near both embankment-abutment junctions. These levels should be verified by an accurate survey and remedial measures implemented. The operability of the sluice gate should be verified. Efforts should also be made to clear embankment overgrowth from both the upstream and downstream slopes. Some concrete deterioration is evident in the spillway and spillway apron which should be repaired along with the rearrangement of displaced riprap observed in the discharge channel. In addition, potential obstructions to free spillway discharge such as the large stump and boat dock section observed in the spillway forebay should be removed.

SECTION 4  
OPERATIONAL PROCEDURES

4.1 Normal Operating Procedure.

The facility is essentially self-regulating. That is, excess inflow discharges automatically over the spillway and is directed downstream. Normally, the outlet conduit is closed. No formal operations manual is available.

4.2 Maintenance of Dam.

No formal maintenance program exists for the dam. The owner stated that responsibility for maintenance of the facility was transferred to Pocono Mountain Lake Estates in exchange for shoreline property and use of the lake.

4.3 Maintenance of Operating Facilities.

The only operable appurtenance associated with the facility is the manually controlled sluice gate at the inlet of the outlet conduit. Regular maintenance is not performed and no maintenance manual is available.

4.4 Warning System.

There is no formal warning system for the facility.

4.5 Evaluation.

No formal operations or maintenance manuals are available for the facility, but are recommended to ensure proper future care and operation. In addition, a formal warning system should be developed and incorporated into any such manuals.

SECTION 5  
HYDROLOGIC/HYDRAULIC EVALUATION

5.1 Design Data.

No formal design reports or calculations are available. A state permit application report for the reconstruction of the dam, dated 1955, indicates that the spillway was designed with a discharge capacity of about 5,370 cfs, based on a spillway opening 110 feet long and 5.5 feet deep (as-built), using 3.78 as the coefficient of discharge. The design capacity exceeded 1955 state requirements and was subsequently approved.

5.2 Experience Data.

Records of reservoir levels and/or spillway discharges are not available.

5.3 Visual Observations.

On the date of inspection, no conditions were observed that would indicate the spillway could not function satisfactorily during a flood event, within the limits of its design capacity.

5.4 Method of Analysis.

The facility has been analyzed in accordance with the procedures and guidelines established by the U. S. Army, Corps of Engineers, Baltimore District, for Phase I hydrologic and hydraulic evaluations. The analysis has been performed utilizing a modified version of the HEC-1 program developed by the U. S. Army, Corps of Engineers, Hydrologic Engineering Center, Davis, California. Analytical capabilities of the program are briefly outlined in the preface contained in Appendix D.

5.5 Summary of Analysis.

a. Spillway Design Flood (SDF). In accordance with the procedures and guidelines contained in the National Guidelines for Safety Inspection of Dams for Phase I Investigations, the Spillway Design Flood (SDF) for Beaver Pond Dam ranges between the 1/2 PMF (Probable Maximum Flood) and the PMF. This classification is based on the relative size of the dam (small) and the potential hazard of dam failure to downstream developments (high). Since the facility is classified near the lower bounds of the small category, the SDF is considered to be the 1/2 PMF.

b. Results of Analysis. Beaver Pond Dam was evaluated under normal operating conditions. That is, the reservoir was initially at its normal pool or spillway elevation of approximately 1172.0 feet, with the spillway weir discharging freely. The outlet conduit was assumed to be non-functional for the purpose of analysis, since the flow capacity of this conduit is not such that it would significantly increase the total discharge capabilities of the dam and reservoir. The spillway consists of an uncontrolled, rectangular shaped, concrete chute channel with discharges regulated by a concrete ogee-type weir.

Lake Rene Dam and Marcel Lake Dam, located upstream of Beaver Pond Dam, were considered in this analysis to determine their effects on Beaver Pond Dam. They also were evaluated under normal operating conditions. That is, the reservoirs were initially at normal pool; the spillways were assumed to be discharging freely; and, the outlet conduits were assumed to be closed. The outflow from Lake Rene Dam was routed directly into Marcel Lake, and the total outflow from Marcel Lake Dam was routed directly into Beaver Pond. All pertinent engineering calculations relative to the evaluation of Beaver Pond Dam, including those pertaining to the upstream facilities, are included in Appendix D.

Overtopping analysis (using the modified HEC-1 computer program) indicated that the discharge/storage capacity of Beaver Pond Dam can accommodate only about 40 percent of the PMF prior to overtopping of the low area in the embankment crest (elevation 1177.4). It is also noted that under events of 0.3 PMF magnitude or greater, discharge would occur around the right abutment, and under events of 0.37 PMF magnitude or greater, discharge would occur around both the left and right abutments (Appendix D, Sheet 13; Summary Input/Output Sheets, Sheet K; Appendix A, "Profile of Dam Crest from Field Survey"). The upstream facilities, Lake Rene Dam and Marcel Lake Dam, can accommodate about 70 percent and 38 percent of the PMF, respectively, prior to embankment overtopping. Under 1/2 PMF (SDF) conditions, the Beaver Pond Dam embankment would be inundated for about 3.0 hours, by depths of up to 0.7 feet above the low area in the embankment crest (Summary Input/Output Sheets, Sheets J and K). Since the SDF for Beaver Pond Dam is the 1/2 PMF, it can be concluded that the dam has a high potential for overtopping, and thus, for breaching under floods of 1/2 PMF magnitude or less.

As Beaver Pond Dam cannot safely accommodate a flood of at least 1/2 PMF magnitude, the possibility of embankment failure under floods of 1/2 PMF intensity or less was investigated (in accordance with Corps directive ETL-1110-2-234). Several possible alternatives were examined, since it is difficult, if not impossible, to determine exactly how or if a specific dam will fail. The major concern of the breaching analysis is with the impact of the various breach discharges on increasing downstream water surface elevations above those to be expected if breaching did not occur.

The modified HEC-1 computer program was used for the breaching analysis, with the assumption that the breaching of an earth dam would commence once the low area in the embankment crest was overtopped. (It was assumed that the discharge around the left and right abutments alone, which would occur prior to the overtopping of the main embankment, would not ultimately lead to the failure of the dam.) Also, in routing the outflows downstream, the channel bed was assumed to be initially dry.

Five breach models were analyzed for Beaver Pond Dam. Two sets of breach geometry were evaluated for each of two failure times (Appendix D, Sheet 18). The two sets of breach sections chosen were considered to be the minimum and maximum probable failure sections. The two failure times (total time for each breach section to reach its final dimensions) under which the two breach sections were investigated were assumed to be a rapid time (0.5 hours) and a prolonged time (3.0 hours), so that a range of this most sensitive variable might be examined. In addition, an average possible set of breach conditions was analyzed, with a failure time of 1.0 hours.

The peak breach outflows (resulting from 0.43 PMF conditions) at Beaver Pond Dam ranged from about 5,570 cfs for the minimum section - maximum fail time scheme to about 8,700 cfs for the maximum section - minimum fail time scheme. The peak outflow resulting from the average breach scheme was about 6,170 cfs, compared to the non-breach 0.43 PMF peak outflow of approximately 5,540 cfs (Appendix D, Sheet 20).

The principal center of damage investigated is at Section 1 (see Figure 1), approximately 500 feet downstream from Beaver Pond Dam, where several small businesses and residences are located. Within this reach, the 0.43 PMF non-breach outflows resulted in a peak water surface elevation of about 2.1 feet above the damage level of the structures. However, the water surface elevations resulting from the breach models were as much as 3.0 feet above the damage level of the structures, representing increases of up to 0.9 feet (Appendix D, Sheet 20).

The consequences of dam failure can better be envisioned if not only the increase in the height of the floodwave is considered, but, also the great increase in momentum of the larger and probably swifter moving volume of water. In addition, there is the possibility of a failure section larger than those analyzed, which could result from a total or partial failure of the spillway weir itself, which could result in even higher downstream water surface elevations.

From this analysis, it is concluded that the failure of Beaver Pond Dam is quite possible, and would most likely lead to increased property damage and possibly to loss of life in the downstream region.

### 5.6 Spillway Adequacy.

As presented previously, Beaver Pond Dam can accommodate only about 40 percent of the PMF prior to embankment overtopping. Should an event of this magnitude or greater occur, the dam would be overtopped and could possibly fail, endangering downstream residents and increasing the potential for loss of life in the downstream regions. Therefore, the spillway is considered to be seriously inadequate.

SECTION 6  
EVALUATION OF STRUCTURAL INTEGRITY

6.1 Visual Observations.

a. Embankment. Based on visual observations, the embankment appeared to be in good condition. A few minor deficiencies were noted at the time of inspection which will require remedial attention. They are:

1. Low areas approximately one-foot below the design crest elevation occur in both the left and right abutments. An accurate survey is recommended and the areas should be regraded consistent with the design top of dam elevation.

2. The roots of trees growing on the dam may increase the seepage potential through the embankment and uprooting of the trees by high winds could cause substantial volume of the embankment material to be displaced. Hence, the trees and their root systems should be removed.

b. Appurtenant Structures.

1. Spillway. The spillway is in good condition with only minor spalling and cracking being observed on the ogee structure and sidewalls. Minor deterioration of the spillway apron was evident which will require patching or grouting. Displaced riprap observed in the discharge channel should be rearranged to provide for maximum erosion protection.

2. Outlet Works. The outlet works appears to be in good condition. No concrete deterioration or corrosion of the valve operator was evident.

6.2 Design and Construction Techniques.

No design or construction records are available with the exception of construction drawings and a few dated photographs contained in PennDER files. A state inspection report, dated July 1956, indicated that construction had been completed in accordance with the plans and specifications.

6.3 Past Performance.

No formal records of past performance are available from the owner; however, information contained in PennDER files suggest that the reconstructed facility has performed satisfactorily since its completion.

#### 6.4 Seismic Stability.

The dam is located in Seismic Zone No. 1 and thus, may be subject to minor earthquake induced dynamic forces. As the overall static stability of the embankment appears adequate, it is believed that the facility can withstand minor earthquake induced dynamic forces. However, no calculations and/or investigations were performed to confirm this opinion.

## SECTION 7

## ASSESSMENT AND RECOMMENDATION FOR REMEDIAL MEASURES

7.1 Dam Assessment.

a. Safety. The results of this evaluation indicate the facility is in good condition.

The size classification of the facility is small and its hazard classification is considered to be high. In accordance with the recommended guidelines, the Spillway Design Flood for the facility ranges between the 1/2 PMF (Probable Maximum Flood) to the PMF. This classification is based on the relative size of the facility (small) and the potential hazard of dam failure to downstream developments (high). Since the facility is classified near the lower bounds of the small category, the SDF is considered to be the 1/2 PMF. Hydraulic and hydrologic analyses indicate the facility will pass and/or store approximately 40 percent of the PMF prior to embankment overtopping at the low area in the embankment crest (elevation 1177.4). Breach analysis indicates that failure under less than 1/2 PMF conditions could lead to increased downstream damage and potential for loss of life. Thus, based on screening criteria provided in the recommended guidelines, the spillway is considered to be seriously inadequate and the facility unsafe, non-emergency.

b. Adequacy of Information. The available information is considered adequate to make an accurate Phase I assessment of the facility.

c. Urgency. The recommendations listed below should be implemented immediately.

d. Necessity for Additional Investigations. Additional investigations are currently deemed necessary to more accurately assess the adequacy of the spillway.

7.2 Recommendations/Remedial Measures.

a. Develop a formal emergency warning system to notify downstream residents should hazardous embankment conditions develop. Included in the plan should be provisions for around-the-clock surveillance of the facility during periods of unusually heavy precipitation.

b. Retain the services of a registered professional engineer experienced in the hydraulics and hydrology of dams to more accurately assess the adequacy of the spillway and prepare recommendations for remedial measures deemed necessary to make the facility hydraulically adequate.

- c. Have the embankment and immediate abutment areas accurately surveyed and infill any low areas to restore the crest to the design elevation of 1177.5 feet.
- d. Repair all areas of deterioration in the concrete surfaces of the spillway and spillway apron, and rearrange any displaced riprap in the discharge channel.
- e. Remove the potentially obstructing debris lodged in the spillway forebay.
- f. Remove all the trees, their root systems, and brush from the crest, upstream and downstream embankment slopes. This operation should be conducted under the guidance of a soils engineer experienced in the design and construction of earth dams.
- g. Develop formal manuals of operation and maintenance to ensure the future proper care of the facility.

APPENDIX A  
VISUAL INSPECTION CHECKLIST AND FIELD SKETCHES

**CHECK LIST  
VISUAL INSPECTION  
PHASE 1**

NAME OF DAM	Beaver Pond Dam	STATE	Pennsylvania
NDI # PA	00408	PENNER #	52-13
TYPE OF DAM	Earth	SIZE	Small
DATE(S) INSPECTION	13 November 1980	WEATHER	Clear
POOL ELEVATION AT TIME OF INSPECTION	1172.1 feet	M.S.L.	
TAILWATER AT TIME OF INSPECTION	N/A	M.S.L.	

**OWNER REPRESENTATIVES**

None

**OTHERS**

B. M. Mihalcin	
D. J. Spaeder	
K. H. Khillji	

RECORDED BY B. M. Mihalcin

**EMBANKMENT**

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS
SURFACE CRACKS	None observed. Embankment crest and downstream embankment slope are primarily grass covered. Many small trees (less than 12 inches in diameter) line the embankment crest on both sides, partially obscuring its view.
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None observed.
SLoughing or eroSION of embankment and abutment slopes	None observed.
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Horizontal - Curved alignment. Vertical - see "Profile of Dam Crest from Field Survey," Appendix A.
RIPRAP FAILURES	None observed. Riprap is hard, well graded sandstone extending to the top of the dam. Excellent condition.
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Good condition at spillway. Cutoff walls evident. No erosion at abutments, but survey indicates abutments are low just beyond embankment contacts.

**EMBANKMENT**

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA • 00408
DAMP AREAS IRREGULAR VEGETATION (LUSH OR DEAD PLANTS)	None observed.	
ANY NOTICEABLE SEEPAGE	None observed.	
STAFF GAGE AND RECORDER	None.	
DRAINS	None observed.	
MISCELLANEOUS	Trees and brush have overgrown both slopes and the crest particularly adjacent to the spillway. Trees and root systems should be removed.	

**OUTLET WORKS**

ITEM	OBSERVATIONS	RECOMMENDATIONS	NDI# P/A -
INTAKE STRUCTURE	Intake tower (concrete) located within reservoir at left end of spillway. Not accessible by foot but appears to be in good condition.		00408
OUTLET CONDUIT (CRACKING AND SPALLING OF CONCRETE SURFACES)	Outlet conduit is 36-inch diameter reinforced concrete pipe. Outlet end is slightly damaged but pipe appears in good condition.		
OUTLET STRUCTURE	Concrete pipe extends through an endwall attached to the left spillway sidewall. Concrete is in good condition.		
OUTLET CHANNEL	Natural channel, possibly lined with rock. Private bridge about 175 feet downstream of spillway will obstruct high discharges. Bridge will probably fail.		
GATE(S) AND OPERATIONAL EQUIPMENT	Rodney Hunt operator located atop intake tower. Inaccessible, but appears to be in good condition.		

**EMERGENCY SPILLWAY**

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA -
TYPE AND CONDITION	Uncontrolled, rectangular shaped, concrete chute channel with an ogee-type weir. Overall condition is good.	00408
APPROACH CHANNEL	Rock lined approach. One large stump and a section of boat dock were lodged in forebay. Should be removed.	
SPILLWAY CHANNEL AND SIDEWALLS	Spillway weir is in good condition. Spillway apron shows some cracking (holes in slab) near right sidewall, but generally good condition. Spillway sidewalls exhibit only minor cracking.	
STILLING BASIN PLUNGE POOL	None. Flow discharges into boulder strewn channel.	
DISCHARGE CHANNEL	Spillway discharges into natural stream. Toe of spillway is protected by concrete endwall. Some riprap appears to be displaced. Should be re-arranged.	
BRIDGE AND PIERS EMERGENCY GATES	None.	

SERVICE SPILLWAY


ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA · 00408
TYPE AND CONDITION	N/A.	
APPROACH CHANNEL	N/A.	
OUTLET STRUCTURE	N/A.	
DISCHARGE CHANNEL	N/A.	

**INSTRUMENTATION**

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDIN PA - 00408
MONUMENTATION SURVEYS	None observed.	
OBSERVATION WELLS	None observed.	
WEIRS	None observed.	
PIEZOMETERS	None observed.	
OTHERS		

**RESERVOIR AREA AND DOWNSTREAM CHANNEL**


ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA - 00408
SLOPES: RESERVOIR	Moderate to steep reservoir slopes. Heavily wooded.	
SEDIMENTATION	None observed.	
DOWNSTREAM CHANNEL (OBSTRUCTIONS, DEBRIS, ETC.)	Private bridge about 175 feet downstream of spillway will obstruct large discharges but will probably fail.	
SLOPES: CHANNEL VALLEY	Steep, narrow and heavily wooded.	
APPROXIMATE NUMBER OF HOMES AND POPULATION	Many homes ( $\approx 15$ ) located along downstream channel between Beaver Pond Dam and Nyce Lake. Two commercial buildings are also located within 500 feet of the dam. It is estimated that as many as 50 persons could be affected by the floodwaters resulting from an embankment breach.	



BEAVER POND DAM  
GENERAL PLAN-FIELD INSPECTION NOTES

**K-E** 20 X 20 TO THE INCH • 7 X 10 INCHES  
KEUFFEL & ESSER CO. MADE IN U.S.A.

46 1242



APPENDIX B  
ENGINEERING DATA CHECKLIST

**CHECK LIST**  
**ENGINEERING DATA**  
**PHASE I**

NAME OF DAM	Beaver Pond Dam	ITEM	REMARKS	NDIN PA. 00408
PERSONS INTERVIEWED AND TITLE		Via phone:	John Eckman, President Eckman Lumber Co. (Owner) R. D. #3 Lehighton, PA 18235	
REGIONAL VICINITY MAP			See Figure 1, Appendix E.	
CONSTRUCTION HISTORY			Constructed in 1956-57 for Camp Massad on Eckman Lumber Co. property. Designed by Edward G. Hess Associates, Inc., of Stroudsburg, Pennsylvania. Constructed by Litz Construction of East Stroudsburg.	
AVAILABLE DRAWINGS			Two drawings available from PennDER files; see Figures 2 and 3 of report. Owner also has set of these drawings.	
TYPICAL DAM SECTIONS			See Figure 3, Appendix E.	
OUTLETS: PLAN DETAILS DISCHARGE RATINGS			See Figures 2 and 3, Appendix E.	

**CHECK LIST**  
**ENGINEERING DATA**  
**PHASE I**  
**(CONTINUED)**

ITEM	REMARKS	NDI#PA • 00408
SPILLWAY: PLAN SECTION DETAILS	See Figures 2 and 3, Appendix E.	
OPERATING EQUIP. MENT PLANS AND DETAILS	See Figure 3, Appendix E.	
DESIGN REPORTS	None available.	
GEOLOGY REPORTS	None.	
DESIGN COMPUTATIONS: HYDROLOGY AND HYDRAULICS STABILITY ANALYSES SEEPAGE ANALYSES	None.	
MATERIAL INVESTIGATIONS: BORING RECORDS LABORATORY TESTING FIELD TESTING	None.	

**CHECK LIST**  
**ENGINEERING DATA**  
**PHASE I**  
**(CONTINUED)**

<b>ITEM</b>	<b>REMARKS</b>	<b>NDIWPA • 00408</b>
<b>BORROW SOURCES</b>	Not known.	
<b>POST CONSTRUCTION DAM SURVEYS</b>	None.	
<b>POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS</b>	None other than PennDER inspections.	
<b>HIGH POOL RECORDS</b>	Not known.	
<b>MONITORING SYSTEMS</b>	None.	
<b>MODIFICATIONS</b>	None indicated.	

**CHECK LIST**  
**ENGINEERING DATA**  
**PHASE I**  
**(CONTINUED)**

ITEM	REMARKS	NDI# PA - 00408
PRIOR ACCIDENTS OR FAILURES	None since re-construction in 1956-57.	
MAINTENANCE: RECORDS MANUAL	None. See "miscellaneous" below.	
OPERATION: RECORDS MANUAL	None.	
OPERATIONAL PROCEDURES	Self-regulating. Facility has been drawn down on occasion. Latest drawdown about two years ago to repair docks.	
WARNING SYSTEM AND/OR COMMUNICATION FACILITIES	None.	
MISCELLANEOUS	Owner (Eckman Lumber Co.) has agreement (in deed) with Pocono Mountain Lake Estates, Development agreed to maintain dam for use of lake and sale of part of shoreline.	

GAI CONSULTANTS, INC.

CHECK LIST  
HYDROLOGIC AND HYDRAULIC  
ENGINEERING DATA

NDI ID # PA-00408  
PENNDR ID # 52-13

SIZE OF DRAINAGE AREA: 7.0 square miles.

ELEVATION TOP NORMAL POOL: 1172.0 STORAGE CAPACITY: 61 acre-feet.

ELEVATION TOP FLOOD CONTROL POOL: - STORAGE CAPACITY: -

ELEVATION MAXIMUM DESIGN POOL: - STORAGE CAPACITY: -

ELEVATION TOP DAM: 1177.4 STORAGE CAPACITY: 150 acre-feet.

SPILLWAY DATA

CREST ELEVATION: 1172.0 feet.

TYPE: Uncontrolled, rectangular shaped, concrete chute channel with ogee-type weir.

CREST LENGTH: 110 feet

CHANNEL LENGTH: N/A

SPILLOVER LOCATION: Right abutment.

NUMBER AND TYPE OF GATES: None.

OUTLET WORKS

TYPE: Rodney Hunt 36-inch diameter sluice gate.

LOCATION: Upstream toe at left sidewall of spillway.

ENTRANCE INVERTS: 1165.0 feet (design).

EXIT INVERTS: 1163.1 feet (field).

EMERGENCY DRAWDOWN FACILITIES: 36-inch diameter sluice gate.

HYDROMETEOROLOGICAL GAGES


TYPE: None.

LOCATION: -

RECORDS: -

MAXIMUM NON-DAMAGING DISCHARGE: Unknown.

APPENDIX C  
PHOTOGRAPHS



BEAVER POND DAM  
PHOTOGRAPH KEY MAP



2



4



1





6



8



5



7



10



9



APPENDIX D  
HYDROLOGIC AND HYDRAULIC ANALYSES

## PREFACE

The modified HEC-1 program is capable of performing two basic types of hydrologic analyses: 1) the evaluation of the overtopping potential of the dam; and 2) the estimation of the downstream hydrologic-hydraulic consequences resulting from assumed structural failures of the dam. Briefly, the computational procedures typically used in the dam overtopping analysis are as follows:

- a. Development of an inflow hydrograph(s) to the reservoir.
- b. Routing of the inflow hydrograph(s) through the reservoir to determine if the event(s) analyzed would overtop the dam.
- c. Routing of the outflow hydrograph(s) from the reservoir to desired downstream locations. The results provide the peak discharge(s), time(s) of occurrence the peak discharge(s), and the maximum stage(s) of each routed hydrograph at the downstream end of each reach.

The evaluation of the hydrologic-hydraulic consequences resulting from an assumed structural failure (breach) of the dam is typically performed as shown below.

- a. Development of an inflow hydrograph(s) to the reservoir.
- b. Routing of the inflow hydrograph(s) through the reservoir.
- c. Development of a failure hydrograph(s) based on specified breach criteria and normal reservoir outflow.
- d. Routing of the failure hydrograph(s) to desired downstream locations. The results provide estimates of the peak discharge(s), time(s) to peak and maximum water surface elevation(s) of failure hydrograph(s) for each location.

HYDROLOGY AND HYDRAULIC ANALYSIS  
DATA BASE


NAME OF DAM: BEAVER POND DAM

PROBABLE MAXIMUM PRECIPITATION (PMP) = 22.0 INCHES/24 HOURS <sup>(1)</sup>

STATION	1	2	3
STATION DESCRIPTION	LAKE RENE DAM	MARCEL LAKE DAM	BEAVER POND DAM
DRAINAGE AREA (SQUARE MILES)	1.6	2.7	2.7
CUMULATIVE DRAINAGE AREA (SQUARE MILES)	1.6	4.3	7.0
ADJUSTMENT OF PMF FOR DRAINAGE AREA LOCATION (%) <sup>(1)</sup>	Zone 1	Zone 1	Zone 1
6 HOURS	111	111	111
12 HOURS	123	123	123
24 HOURS	133	133	133
48 HOURS	142	142	142
72 HOURS	-	-	-
SNYDER HYDROGRAPH PARAMETERS			
ZONE (2)	1	1	1
$C_p$ (3)	0.45	0.45	0.45
$C_t$ (3)	1.23	1.23	1.23
$L$ (MILES) (4)	2.5	2.7	3.3
$L_{ca}$ (MILES) (4)	1.2	1.2	1.4
$t_p = C_t (L \cdot L_{ca})^{0.3}$ (HOURS)	1.71	1.75	1.95
SPILLWAY DATA (5)			
CREST LENGTH (FEET)	55	60	110
FREEBOARD (FEET)	5.0	5.5	5.4

- (1) HYDROMETEOROLOGICAL REPORT 33, U.S. ARMY CORPS OF ENGINEERS, 1956.
- (2) HYDROLOGIC ZONE DEFINED BY CORPS OF ENGINEERS, BALTIMORE DISTRICT, FOR DETERMINATION OF SNYDER COEFFICIENTS ( $C_p$  AND  $C_t$ ).
- (3) SNYDER COEFFICIENTS
- (4)  $L$  = LENGTH OF LONGEST WATERCOURSE FROM DAM TO BASIN DIVIDE  
 $L_{ca}$  = LENGTH OF LONGEST WATERCOURSE FROM DAM TO POINT OPPOSITE BASIN CENTROID.
- (5) SPILLWAY DATA RELATING TO LAKE RENE DAM AND MARCEL LAKE DAM OBTAINED FROM PHASE I INSPECTION REPORT, MARCEL LAKE DAM (SEE NOTE 3, SHEET 14 OF 20).

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 1-29-81 PROJ. NO. 80-238-408  
CHKD. BY DJA DATE 3-4-81 SHEET NO. 1 OF 20



## DAM STATISTICS

HEIGHT OF DAM = 14 FT (FIELD MEASURED: TOP OF DAM TO D.S. OUTLET INVERT; "TOP OF DAM" HERE AND ON ALL SUBSEQUENT CALCULATION SHEETS REFERS TO THE LOW AREA IN THE EMBANKMENT CREST.)

NORMAL POOL STORAGE CAPACITY =  $20 \times 10^6$  GALLONS  
= 61.4 AC-FT (SEE NOTE 1)

MAXIMUM POOL STORAGE CAPACITY = 149.8 AC-FT (SEE NOTE 4)  
(@ TOP OF DAM)

### DRAINAGE AREA:

LAKE REVE SUB-BASIN: 1.6  
MARCEL LAKE LOCAL SUB-BASIN: 2.7  
BEAVER DAM LOCAL SUB-BASIN: 2.7  
TOTAL: 7.0 SQUARE MILES

(PLUMMETERED ON USGS 7.5' topo quads - EIGEMERE,  
AND LAKE MASKINOGHA, PA)

### ELEVATIONS:

TOP OF DAM (DESIGN)	= 1177.5	(FIG. 3; SEE NOTE 2)
TOP OF DAM (FIELD)	= 1177.4	
NORMAL POOL	= 1172.0	(SEE NOTE 2)
SPILLWAY CREST	= 1172.0	(FIG. 3; SEE NOTE 2)
UPSTREAM INLET INVERT (DESIGN)	= 1165.0	(FIG. 3; SEE NOTE 2)
DOWNSTREAM OUTLET INVERT (DESIGN)	= 1164.6	(FIG. 3; SEE NOTE 2)
DOWNSTREAM OUTLET INVERT (FIELD)	= 1163.1	
STREAMBED @ DAM CENTERLINE	= 1164.6	(ESTIMATED FROM FIG. 3; SEE NOTE 2)

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 1-29-81 PROJ. NO 80-238-408  
CHKD. BY DLG DATE 3-4-81 SHEET NO. 2 OF 22

CONSULTANTS, INC.  
Engineers • Geologists • Planners  
Environmental Specialists

NOTE 1: OBTAINED FROM "REPORT UPON THE APPLICATION OF MASSAD  
CAMS, INC., FOR THE RECONSTRUCTION OF A DAM ACROSS  
DAGMAR'S CREEK, IN DELAWARE TOWNSHIP, PA. COUNTY;"  
NOVEMBER, 1955; FOUND IN PERUNDER FILES.

NOTE 2: THE DESIGN DRAWINGS ARE BASED IN A NORMAL POOL OR  
SPILLWAY ELEVATION OF 99.4 FEET. THE USGS TOPO QUAD FOR  
EDGEMERE, PA, INDICATES THE NORMAL POOL ELEVATION IS  
SOMewhere BETWEEN 1160.0 AND 1180.0. IT WILL BE ASSUMED  
THAT THE SPILLWAY CREST IS AT ELEVATION 1173.3, AND THIS  
1072.6 FEET (OR 1172.0 - 99.4) WILL BE ADDED TO ALL THE  
ELEVATIONS INDICATED ON THE DESIGN DRAWINGS. (THE VALUE 172 WAS  
ASSUMED, IN ORDER TO BEST MATCH THE RESULTS OF THE FIELD  
SURVEY WITH THE CONTOURS IN THE USGS TOPO MAP. IT IS NOTED THAT  
THE ELEVATIONS USED IN THIS ANALYSIS ARE CONSIDERED ESTIMATES,  
AND ARE NOT NECESSARILY ACCURATE.)

### DAM CLASSIFICATION

DAM SIZE: SMALL (REF 1, TABLE 1)

HAZARD CLASSIFICATION: HIGH (FIELD OBSERVATION)

REQUIRED SDF: 1/6 PMF TO PMF (REF 1, TABLE 3)

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 1-29-81 PROJ. NO. 80-238-408  
CHKD. BY DG DATE 3-4-81 SHEET NO. 3 OF 20



## HYDROGRAPH PARAMETERS

FOR LOCAL SUB-DRAIN:

LENGTH OF LONGEST WATERCOURSE:  $L = \underline{3.3 \text{ MILES}}$

LENGTH OF LONGEST WATERCOURSE FROM DAM TO A  
POINT OPPOSITE BASIN CENTROID:  $L_{CA} = \underline{1.4 \text{ MILES}}$

(MEASURED ON USGS TOPO QUAD: EDGEMERE, AND  
LAKE MASKENOZHA, PA)

$$C_c = .23$$

$$C_p = 1.45$$

(JUPPED BY C.O.E., ZONE 1,  
DELAWARE RIVER BASIN)

INDEX STANDARD LAG:

$$t_p = C_c (L \cdot L_{CA})^{0.3}$$

$$= 1.23 (3.3 \times 1.4)^{0.3}$$

$$= \underline{1.75 \text{ HOURS}}$$

(NOTE: HYDROGRAPH VARIABLES USED HERE ARE DEFINED IN REF. 2,  
IN SECTION ENTITLED "SNYDER SYNTHETIC UNIT HYDROGRAPH.")

## RESERVOIR CAPACITY

RESERVOIR SURFACE AREAS:

AREA AREA (SA) @ NORMAL POOL (EL 11720) = 13 ACRES

SA @ EL 1180 = 23 ACRES

SA @ EL 1200 = 72 ACRES

(USGS TOPO QUAD: EDGEMERE & LAKE MASKENOZHA)

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJT DATE 1-29-81 PROJ. NO. 80-238-408  
CHKD. BY DLB DATE 3-4-81 SHEET NO. 4 OF 20



S.A. @ TOP OF DAM (EL. 1177.4) = 19.8 ACRES  
(BY LINEAR INTERPOLATION)

IT IS ASSUMED THAT THE MODIFIED PRISMOIDAL RELATIONSHIP  
ADEQUATELY MODELS THE RESERVOIR SURFACE AREA-STORAGE RELATIONSHIP:

(REF 14, p. 15)

$$\Delta V_{1-2} = \frac{h}{3} (A_1 + A_2 + \sqrt{A_1 \cdot A_2})$$

WHERE  $\Delta V_{1-2}$  = INCREMENTAL HEAD BETWEEN ELEVATIONS 1 + 2, IN AC-FT,  
 $h$  = ELEVATION 1 - ELEVATION 2, IN FT,  
 $A_1$  = S.A. @ ELEVATION 1, IN ACRES,  
 $A_2$  = S.A. @ ELEVATION 2, IN ACRES.

IT IS ALSO ASSUMED THAT THE SURFACE AREA VARIES LINEARLY  
BETWEEN THE ELEVATIONS INDICATED ABOVE.

ELEVATION - STORAGE RELATIONSHIP:

ELEVATION (FT)	A <sub>1</sub> (AC)	$\Delta V_{1-2}$ (AC-FT)	TOTAL VOLUME (AC-FT)
1165.0 ( <sup>TOP</sup> <sub>POOL</sub> )	0	—	0 *
1172.0	13	—	61.4 *
1174.0	15.5	28.5	89.9
1176.0	18.0	33.5	123.4
1177.4 ( <sup>TOP</sup> <sub>DAM</sub> )	19.8	36.4	149.8
1178.0	20.5	12.1	161.9
1180.0	23	43.5	205.4
1182.0	27.9	50.8	256.2
1185.0	35.3	94.6	350.8

\* ZERO-STORAGE ELEVATION AND NORMAL POOL STORAGE CAPACITY  
FROM SHEET 1.

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 1-29-81 PROJ. NO. 80-238-408  
CHKD. BY DLO DATE 3-4-81 SHEET NO. 5 OF 20



### PMP CALCULATIONS

APPROXIMATE RAINFALL INDEX = 22.0 INCHES  
(CORRESPONDING TO A DURATION OF 24 HOURS AND A  
DRAINAGE AREA OF 200 SQUARE MILES)

(REF. 3, FIG. 1)

DEPTH-AREA-DURATION ZONE 1

(REF. 3, FIG. 1)

ASSUME DATA CORRESPONDING TO A 10-SQUARE MILE AREA  
MAY BE APPLIED TO THIS 2.7 SQUARE MILE BASIN:

<u>DURATION (HRS)</u>	<u>PERCENT OF INDEX RAINFALL</u>
6	111
12	123
24	133
48	142

(REF. 3, FIG. 2)

Hop Brook Factor (ADJUSTMENT FOR BASIN SHAPE AND FOR THE LOWER  
LIKELIHOOD OF A SEVERE STORM CENTERING OVER A SMALL BASIN) FOR  
A DRAINAGE AREA OF 2.7 SQUARE MILES IS 0.80.


(Ref 4, p 48)

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 1-29-81 PROJ. NO. 80-228-408  
CHKD. BY DLB DATE 3-4-81 SHEET NO. 6 OF 20




### SPILLWAY CAPACITY

CROSS-SECTION: - LOOKING UPSTREAM -



- NOT TO SCALE -

### PROFILE:



- NOT TO SCALE -

SKETCHES BASED ON FIELD NOTES AND  
ON FIG. 3.

THE SPILLWAY CONSISTS OF A RECTANGULAR-SHAPED CONCRETE CHUTE CHANNEL WITH A CONCRETE Ogee-TYPE WEIR, AS SKETCHED ABOVE.

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 1-29-81 PROJ. NO. 80-238-408  
CHKD. BY DLS DATE 2-4-81 SHEET NO. 7 OF 20



DISCHARGE CAN BE ESTIMATED BY THE EQUATION

$$Q = CLH^{3/2} \quad (\text{REF 4, p. 373})$$

WHERE  $Q$  = DISCHARGE, IN CFS,  
 $C$  = COEFFICIENT OF DISCHARGE,  
 $L$  = LENGTH OF WEIR CREST = 110 FT,  
 $H$  = HEAD, IN FT.

THE DESIGN HEAD,  $H_0$ , IS ASSUMED TO BE 5.5 FEET, OR TO THE TOP OF THE SPILLWAY WINGWALLS. IT IS ASSUMED THAT THE RELATIONSHIPS IN REF 4, PP. 372-382, CAN BE APPLIED TO THIS OGEE-TYPE WEIR. FOR A FOREBAY DEPTH OF 2.5 FEET,

$$\frac{P}{H_0} = \frac{2.5}{5.5} = 0.45$$

$$\therefore C_0 = 3.78 \quad (\text{REF 4, p. 378, FIG. 249})$$

APPROACH CHANNEL LOSSES @ DESIGN HEAD DISCHARGE:

APPROACH CHANNEL LENGTH = 16.0 FT

APPROACH CHANNEL WIDTH = 110 FT

AT EL. 117.5 (DESIGN POOL),

AVERAGE APPROACH CHANNEL DEPTH = 2.5 + 5.5 = 8.0 FT

FLOW AREA = 8.0 x 110 = 880 FT<sup>2</sup>

- INITIAL ESTIMATE OF DISCHARGE:

$$Q = CLH^{3/2} = (3.78)(110)(5.5)^{3/2} = \underline{5363} \text{ CFS}$$

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DTS DATE 1-30-81 PROJ. NO. 80-238-408  
CHKD. BY DLB DATE 3-4-81 SHEET NO. 8 OF 20



- AVERAGE VELOCITY IN APPROACH CHANNEL :

$$V_A = \frac{Q}{A} = \frac{5363}{880} = 6.1 \text{ FPS}$$

- AVERAGE APPROACH VELOCITY HEAD :

$$h_A = \frac{V_A^2}{2g} = \frac{(6.1)^2}{64.4} = 0.58 \text{ FT}$$

- ASSUMING THAT THE APPROACH CHANNEL ENTRANCE LOSS =  $0.1 h_A$  (REF 4, p. 379)

$$h_E = \text{ENTRANCE LOSS} = (0.1)(0.58) = 0.06 \text{ FT}$$

- APPROACH CHANNEL FRICTION LOSS,  $h_F$  :

$$h_F = \left[ \frac{V_A n}{1.486 R^{2/3}} \right]^2 \times L_C \quad (\text{REF 4, p. 379})$$

WHERE  $L_C$  = LENGTH OF APPROACH CHANNEL = 16.0 FT,

$n$  = MANNING'S ROUGHNESS COEFFICIENT = 0.035,  
(COMPPOSITE ; FIELD OBSERVATION)

$R$  = HYDRAULIC RADIUS = FLOW AREA / WETTED PERIMETER.

WETTED PERIMETER :

$$\text{AVG. HT. OF WINGWALL} = \frac{(1.0)(8.0) + (15.0)(\frac{8.0 + 0.5}{2})}{16.0} = 4.5 \text{ FT}$$

$$\therefore \text{AVG WETTED PERIMETER} = 2(4.5) + 110 = 119.0 \text{ FT}$$

$$\text{AVG. HYDRAULIC RADIUS} = R_H = \frac{A}{P} = \frac{880}{119} = 7.4 \text{ FT}$$

$$\therefore h_F = \left[ \frac{(6.1)(0.035)}{(1.486)(7.4)^{2/3}} \right]^2 \times 16.0 = 0.02 \text{ FT}$$

$$\therefore \text{TOTAL APPROACH LOSS} = 0.02 + 0.06 = 0.08 \text{ FT}$$

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 1-30-81 PROJ. NO. 80-238-408  
CHKD. BY DLO DATE 3-4-81 SHEET NO. 9 OF 20



ACTUAL EFFECTIVE HEAD:  $h_e = 5.5 - 0.08 = 5.42 \text{ FT}$

$$\begin{aligned} \text{SPILLWAY CAPACITY @ DESIGN HEAD} &= (3.78)(110)(5.42)^{3/2} \\ &= \underline{5247 \text{ CFS}} \end{aligned}$$

- FOR HEADS OTHER THAN DESIGN HEAD, THE APPROACH CHANNEL LOSSES WILL BE ASSUMED TO BE PROPORTIONAL TO THE LOSSES AT DESIGN HEAD:

$$h_e = \left(\frac{0.08}{5.5}\right)H$$

WHERE  $h_e$  = TOTAL APPROACH CHANNEL LOSS, IN FT,  
 $H$  = RESERVOIR ELEVATION - 1178.0 FT.

#### EFFECTS OF HEAD OTHER THAN DESIGN HEAD:

AS THE HEAD ON THE WEIR BECOMES SMALL, DISCHARGE IS REDUCED DISPROPORTIONATELY, DUE TO THE ROUGHNESS AND THE CONTACT PRESSURE BETWEEN THE WATER AND THE WEIR SURFACE. THUS, THE DISCHARGE COEFFICIENT ( $C$ ) TAKES ON A LOWER VALUE THAN THAT OF DESIGN HEAD. THE OPPOSITE TREND OCCURS FOR HEADS GREATER THAN THAT OF DESIGN. THEREFORE, THE DESIGN DISCHARGE COEFFICIENT WILL BE MODIFIED APPROPRIATELY, ACCORDING TO FIG. 250, REF. 4.

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 1-30-81 PROJ. NO. 80-038-408  
CHKD. BY DGB DATE 3-4-81 SHEET NO. 10 OF 20



SPILLWAY RATING CURVE:

RESERVOIR ELEVATION (FT)	H (FT)	H/H <sub>0</sub> <sup>①</sup>	S/C <sub>0</sub> <sup>②</sup>	C <sup>③</sup>	ESTIMATED APPROACH LOSS, h <sub>L</sub> <sup>④</sup> (FT)	EFFECTIVE HEAD, H <sub>E</sub> <sup>⑤</sup> (FT)	Q <sup>⑥</sup> (cfs)
1172.0	0	0	—	—	—	—	0
1173.0	1.0	0.18	0.85	3.21	0.01	0.99	350
1174.0	2.0	0.36	0.89	3.36	0.03	1.97	1020
1175.0	3.0	0.55	0.93	3.52	0.04	2.96	1970
1176.0	4.0	0.73	0.96	3.63	0.06	3.94	3120
1177.0	5.0	0.91	0.99	3.74	0.07	4.93	4500
( <sup>TOP</sup> <sup>DAM</sup> ) 1177.4	5.4	0.98	1.00	3.78	0.08	5.32	5100
1177.5	5.5	1.00	1.00	3.78	0.08	5.42	5250
1178.0	6.0	1.09	1.01	3.82	0.09	5.91	6040
1179.0	7.0	1.27	1.03	3.89	0.10	6.90	7760
1180.0	8.0	1.45	1.05	3.97	0.12	7.88	9660
1181.0	9.0	1.64	1.07	4.04	0.13	8.87	11,740
1182.0	10.0	1.82	1.07	4.04	0.15	9.85	13,740
1183.0	11.0	2.00	1.07	4.04	0.16	10.84	15,860
1184.0	12.0	2.18	1.07	4.04	0.17	11.83	18,080
1185.0	13.0	2.36	1.07	4.04	0.19	12.81	20,380

① H<sub>0</sub> = DESIGN HEAD = 5.5 FT

② S/C<sub>0</sub> FROM REG 4, FIG. 250, p. 378.

③ C<sub>0</sub> = 3.78; C = 3.78 x S/C<sub>0</sub>

④ h<sub>L</sub> =  $(\frac{0.08}{5.5})H$  (SEE SHEET 9)

⑤ H<sub>E</sub> = H - h<sub>L</sub>

⑥ Q = CLH<sub>E</sub><sup>3/2</sup>; L = 110 FT; (COMPUTED TO NEAREST 10 CFS).

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 2-2-81 PROJ. NO. 80-238-408  
CHKD. BY DLB DATE 3-4-81 SHEET NO. 11 OF 20



### EMBANKMENT RATING CURVE

ASSUME THAT THE EMBANKMENT BEHAVES ESSENTIALLY AS A BROAD-CRESTED WEIR WHEN OVERTOPPING OCCURS. THUS, THE DISCHARGE CAN BE ESTIMATED BY THE RELATIONSHIP

$$Q = CLH^{2/3} \quad (\text{REF 5, p. 5-23})$$

WHERE  $Q$  = DISCHARGE OVER EMBANKMENT, IN CFS,  
 $L$  = LENGTH OF EMBANKMENT OVERTOPPED, IN FT,  
 $H$  = HEAD, IN FT; IN THIS CASE IT IS THE AVERAGE "FLOW AREA WEIGHTED" HEAD ABOVE THE DAM,  
 $C$  = COEFFICIENT OF DISCHARGE, DEPENDENT UPON THE HEAD AND THE WEIR BREADTH.

### LENGTH OF EMBANKMENT INUNDATED VS. RESERVOIR ELEVATION:

ELEVATION (FT)	LENGTH (FT)
(LOW AREA IN NARROW GROUND NEAR RIGHT ADJUTMENT) 1176.4	0
(TOP OF DAM) 1177.4	50
1177.5	100
1177.7	230
1177.9	280
1178.0	320
1178.5	360
1179.0	370
1180.0	390
1181.0	410
1182.0	430

(FROM FIELD SURVEY AND USGS topo QUAD - EDGEMERE, PA)

SUBJECT

## DAM SAFETY INSPECTION

BEAVER POND DAM

BY DJSDATE 2-2-81PROJ. NO. 80-238-408CHKD. BY DLODATE 3-4-81SHEET NO. 12 OF 20Engineers • Geologists • Planners  
Environmental Specialists

ASSUME THAT INCREMENTAL DISCHARGES OVER THE EMBANKMENT FOR SUCCESSIVE RESERVOIR ELEVATIONS ARE APPROXIMATELY TRAPEZOIDAL IN CROSS-SECTIONAL FLOW AREA. THEN ANY INCREMENTAL AREA OF FLOW CAN BE ESTIMATED AS  $H_i [ (L_1 + L_2)/2 ]$ , WHERE  $L_1$  = LENGTH OF OVERTOPPED EMBANKMENT AT HIGHER ELEVATION,  $L_2$  = LENGTH AT LOWER ELEVATION,  $H_i$  = DIFFERENCE IN ELEVATIONS. THUS, THE TOTAL AVERAGE "FLOW AREA WEIGHTED" HEAD CAN BE ESTIMATED AS  $H_w = (TOTAL FLOW AREA/L_1)$ .

## EMBANKMENT RATING TABLE :

RESERVOIR ELEVATION (FT)	$L_1$ (FT)	$L_2$ (FT)	INCREMENTAL HEAD, $H_i$ (FT)	INCREMENTAL FLOW AREA, $A_i$ ( $FT^2$ )	TOTAL FLOW AREA, $A_t$ ( $FT^2$ )	WEIGHTED HEAD, $H_w$ (FT)	$\frac{H_w}{I}$	$C$	$Q$ (cfs)
(LOW SPOT NEAR RT. AQUITAIN)	1176.4	0	—	0	—	—	—	—	—
(TOP OF DAM)	1177.4	50	0	1.0	25	25	0.50	0.05	3.02 50
	1177.5	100	50	0.1	8	33	0.33	0.03	3.00 60
	1177.7	230	100	0.2	33	66	0.29	0.03	2.99 110
	1177.9	280	230	0.2	51	117	0.42	0.04	3.01 230
	1178.0	320	280	0.1	30	147	0.46	0.05	3.02 300
	1178.5	360	320	0.5	170	317	0.88	0.09	3.03 900
	1179.0	370	360	0.5	183	500	1.4	0.14	3.04 1860
	1180.0	390	370	1.0	380	880	2.3	0.23	3.08 4190
	1181.0	410	390	1.0	400	1280	3.1	0.31	3.09 6910
	1182.0	430	410	1.0	420	1700	4.0	0.40	3.09 10,630

$$\textcircled{1} \quad A_i = H_i [ (L_1 + L_2)/2 ]$$

$$\textcircled{2} \quad H_w = A_t / L_1$$

$\textcircled{3} \quad I = \text{BREADTH OF OVERTOP} = 10 \text{ FT (ASSUMED AVG. VALUE; FIELD MEASURED).}$

$\textcircled{4} \quad C = A(H, I); \text{ FROM REF 12, FIG 24.}$

$\textcircled{5} \quad Q = CL, H_w^{3/2} \text{ (TO NEAREST 10 CFS)}$

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY ZJG DATE 2-2-81 PROJ. NO. 80-238-408  
CHKD. BY DLC DATE 3-4-81 SHEET NO. 13 OF 20



TOTAL FACILITY RATING TABLE

$$Q_{\text{TOTAL}} = Q_{\text{SPILLWAY}} + Q_{\text{PERMANENT}}$$

RESERVOIR ELEVATION (FT)	Q <sup>①</sup> (CFS)	Q <sup>②</sup> (CFS)	Q <sup>③</sup> (CFS)
1172.0	0	—	0
1173.0	350	—	350
1174.0	1020	—	1020
1175.0	1970	—	1970
1176.0	3120	—	3120
1176.4	3670*	0	3670
1177.0 (TOP OF DAM)	4500	30 <sup>*,**</sup>	4530 <sup>**</sup>
1177.4	5100	50	5150
1177.5	5850	60	5310
1177.7	5570*	110	5680
1177.9	5880*	230	6110
1178.0	6040	300	6340
1178.5	6900*	900	7800
1179.0	7760	1860	9620
1180.0	9660	4190	13,850
1181.0	11,740	6910	18,650
1182.0	13,740	10,630	24,370

① FROM SHEET 10.

② FROM SHEET 12.

\* - BY LINEAR INTERPOLATION

\*\* - DISCHARGE AROUND THE ADJUSTMENTS INCLUDED FOR ELEVATIONS ABOVE 1176.4.

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DTS DATE 2-3-81 PROJ. NO. 80-238-408  
CHKD. BY DLG DATE 3-4-81 SHEET NO. 14 OF 20



## UPSTREAM DAMS:

### 1.) Lake Rene Dam

#### - Snyder Unit Hydrograph Parameters:

$$\begin{aligned}
L &= 2.5 \text{ MILES} \\
L_{ca} &= 1.2 \text{ MILES} \\
C_p &= 0.45 \\
C_t &= 1.23 \\
T_p &= 1.23(2.5 \times 1.2)^{0.3} = 1.71 \text{ HOURS}
\end{aligned}$$

(SEE SHEET 3)

- PMP DATA - SEE SHEET 5.

- STORAGE - OUTFLOW RELATIONSHIP: (SEE NOTE 3)

ELEVATION (FT)	STAGE ABOVE NORMAL POOL (FT)	SURCHARGE STORAGE (AC-FT)	OUTFLOW (CFS)
1260.0 (ASSUMED NORMAL POOL)	0	0	0
1261.0	1	79	182
1262.0	2	158	513
1263.0	3	237	943
1264.0	4	316	1452
1265.0 (TOP OF DAM)	5	395	2029
1266.0	6	474	5457
1267.0	7	553	11,253

NOTE 3: Obtained from "Phase I Inspection Report," National Dam  
 Inspection Program, Marcel Lake Dam, NDI-PA 00402, PA-DER 52-149,  
 prepared by O'Brien and Gere; March, 1979.

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DSS DATE 2-3-81 PROJ. NO. 80-238-408  
CHKD. BY DLB DATE 3-4-81 SHEET NO. 15 OF 20



## 2.) MARCEL LAKE DAM

### - SNYDER UNIT HYDROGRAPH PARAMETERS:

$$L = 2.7 \text{ MILES}$$

$$L_{ca} = 1.2 \text{ MILES}$$

$$C_p = 0.45$$

$$C_t = 1.23$$

$$T_p = 1.03 (2.7 \times 1.2)^{0.3} = 1.75 \text{ HOURS}$$

(SEE SHEET 3)

### - PMP DATA - SEE SHEET 5.

### - ELEVATION-STORAGE RELATIONSHIP:

- COMPUTED INTERNALLY IN THE HEC-1 PROGRAM, VIA CONIC METHOD,  
BASED ON THE FOLLOWING SURFACE AREA DATA (SEE NOTE 3):

ELEVATION (FT)	SURFACE AREA (ACRES)
1215 (NORMAL POOL)	0
1231	27
1240	37
1260	78

- NORMAL POOL ELEVATION = 1231.0

- TOP OF DAM ELEVATION = 1236.5

(SEE NOTE 3)

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 2-7-81 PROJ. NO. 80-238-408  
CHKD. BY DLG DATE 3-4-81 SHEET NO. 16 OF 20



MARCEL LAKE DAM:

FACILITY RATING CURVE: (SEE NOTE 3)

(NORMAL POOL) ( <sup>TOP OF</sup> DAM)	ELEVATION (FT)	OUTFLOW (CFS)
	1231.0	0
	1232.0	222
	1233.0	628
	1234.0	1154
	1235.0	1776
	1236.0	2482
	1236.5	2863
	1237.5	4609
	1238.5	8120
	1239.5	12,964

(NOTE: IT IS ASSUMED IN THIS ANALYSIS THAT SILVER LAKE, A NATURAL LAKE WITHIN THE MARCEL LAKE WATERSHED, HAS NO IMPACT ON REDUCING THE DEAK INFLOW INTO MARCEL LAKE.)

SUBJECT	BEAVER Pond Dam
BY	2005
CHKD BY	DATE 3-4-81
PROJECT NO. 20-238-42	

### DOWNSTREAM ROUTING SECTION

- SECTION I, 500 FT U.S. OF BEAVER DAM


INVERT = 1161.0

CHANNEL SLOPE = 0.010

$n_{200} = 0.070$ ;  $n_{400} = 0.080$

$n_{60} = 0.035$

(DAMAGE LEVEL @ EL. 1167)




NOTE: SECTION BASED ON FIELD NOTES AND OBSERVATIONS AND  
USGS TOPO QUAD - FOREMERE, PA. ELEVATIONS ARE  
CONSIDERED ESTIMATES, AND ARE NOT NECESSARILY  
ACCURATE.

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DTS DATE 2-27-81 PROJ. NO. 80-238-408  
CHKD. BY DLO DATE 3-4-81 SHEET NO. 18 OF 20



## BREACH ASSUMPTIONS

### TYPICAL BREACH SECTION:



### HEC-1 BREACHING ANALYSIS INPUT:

<u>PLAN</u>	<u>BREACH BOTTOM WIDTH (FT)</u>	<u>MAX BREACH DEPTH (FT)</u>	<u>SECTION SIDE-SLOPES</u>	<u>BREACH TIME (HRS)</u>	<u>WSEL @ START OF FAILURE (FT)</u>
① MIN. BREACH SECTION, MIN. FAIL TIME	10	12.4	1H:1V	0.5	1177.4
② MAX. BREACH SECTION, MIN. FAIL TIME	40	12.4	10:1	0.5	1177.4
③ MIN BREACH SECTION MAX FAIL TIME	10	12.4	1:1	3.0	1177.4
④ MAX BREACH SECTION MAX FAIL TIME	40	12.4	10:1	3.0	1177.4
⑤ AVERAGE POSSIBLE CONDITIONS	20	12.4	1:1	1.0	1177.4

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DTS DATE 2-27-81 PROJ. NO. 80-238-408  
CHKD. BY DLB DATE 3-4-81 SHEET NO. 19 OF 20



THE BREACH ASSUMPTIONS LISTED ON THE PRECEDING  
SHEET ARE BASED ON THE SUGGESTED RANGES PROVIDED BY  
THE C.O.E. (BALTIMORE DISTRICT), AND ON THE PHYSICAL CONSTRAINTS  
OF THE DAM AND SURROUNDING TERRAIN:

- DEPTH OF BREACH OPENING = 12.4 FT (TOP OF DAM TO MINIMUM  
RESERVOIR ELEVATION)
- LENGTH OF BREACHABLE EMBANKMENT = 385 FT (FIELD MEASURED)
- VALLEY BOTTOM WIDTH = 150 FT (FIELD OBSERVATION; THE  
SPILLWAY CREST IS 110 FT LONG, ∴ MAXIMUM BREACH BOTTOM  
WIDTH FOR HEC-1 INPUT = 40 FT.)
- VALLEY SIDE-SLOPES ADJACENT TO DAM:

RIGHT SIDE: 10 H:1 V  
LEFT SIDE: 10 H:1 V  
(FIELD SURVEY AND USGS TOPO  
QUAD, EDGEWATER, PA)

SUBJECT DAM SAFETY INSPECTIONBEAVER POND DAMBY DJS DATE 7-4-81 PROJ. NO. 80-238-408CHKD. BY DLB DATE 3-5-81 SHEET NO. 20 OF 20CONSULTANTS, INC.  
Engineers • Geologists • Planners  
Environmental SpecialistsHEC-1 DAM BREACHING ANALYSIS OUTPUTBEAVER DAM DATA: (UNDER 0.43 PMF CONDITIONS)

PLAN	VARIABLE BREACH BOTTOM WIDTH (FT)	ACTUAL MAX. FLOW DURING FAIL TIME (CFS)	CORRESPONDING TIME OF PEAK (HRS)	INTERPOLATED OR HEC-1 ROUTED MAX. FLOW DURING FAIL TIME (CFS)	CORRESPONDING TIME OF PEAK (HRS)	ACTUAL PEAK FLOW THROUGH DAM (CFS)	CORRESPONDING TIME OF PEAK (HRS)	TIME OF INITIAL BREACH (HRS)
①	10	6490	42.17	6490	42.17	6490	42.17	41.67
②	40	8701	42.17	8701	42.17	8701	42.17	41.67
③	10	5579	42.28	5578	42.33	5579	42.28	41.67
④	40	5761	42.44	5761	42.50	5761	42.44	41.67
⑤	20	6173	42.67	6173	42.67	6173	42.67	41.67

(NON-BREACH 0.43 PMF PEAK OUTFLOW = 5535 CFS)DOWNSTREAM ROUTING DATA: (UNDER 0.43 PMF CONDITIONS)

OUTPUT @ SECTION 1: 500 FT D.S. FROM DAM:

PLAN	VARIABLE BREACH BOTTOM WIDTH (FT)	PEAK FLOW (CFS)	CORRESPONDING W.S. EL. * (FT)	W.S. EL. * W/O BREACH (FT)	ELEVATION DIFFERENCE (FT)
①	10	6433	1169.4	1169.1	+0.3
②	40	8645	1170.0	1169.1	+0.9
③	10	5579	1169.1	1169.1	0.0
④	40	5760	1169.2	1169.1	+0.1
⑤	20	6166	1169.3	1169.1	+0.2

(NON-BREACH 0.43 PMF PEAK OUTFLOW = 5533 CFS)

\* FROM SUMMARY INPUT/OUTPUT SHEETS, SHEET R.

NOTE: DAMAGE LEVEL OF NEARBY STRUCTURES @ SECTION 1 = 1167 FT.

SUBJECT

# DAM SAFETY INSPECTION

## BEAVER POND DAM

BY

DATE 7-9-81

PROJ. NO. 80-238-408

CHKD. BY

DATE 3-10-81


**GAI**  
**CONSULTANTS, INC.**
Engineers • Geologists • Planners  
Environmental Specialists

### SUMMARY INPUT/OUTPUT SHEETS

## OVERTOPPING ANALYSIS

DAM SAFETY INSPECTION  
BEAVER DAM, W/U.S. LAKE NEME AND MARCEL LAKE DAMS - OVERTOPPING ANALYSIS  
10-MINUTE TIME STEP AND 48-HOUR SIMULATION

NU	MIN	MAX	DAY	IMR	IMIN	IMTC	IPHI	IPHT	MINAN
20H	0	10	0	0	0	0	0	0	0
				DEPTH	NET	DEPTH			
				5	0	0			

MULTI-PLAN ANALYSIS TO BE PERFORMED  
NPOLR= 1 NPLR= 5 NTITR= 1

RATIO= .10 .40 .50 .60 1.00

SUB-AREA RUNOFF COMPUTATION									
NAME, RENE, INTEN, HYDROGRAPH									
ISIAJ	ISIAJ	ICUMP	ICUMC	ISIAF	ISIAF	IPJUT	JPJUT	ISNAME	ISNAME
RENE	RENE	0	0	0	0	0	0	0	0

HYDROGRAPH DATA									
THUG	THUG	LAHFA	BNAP	FRSDA	TRFC	RAILU	ISNU#	ISNAME	LOCAL
1	1	1.60	0.00	7.00	0.00	0.000	0	1	0

PRECIP DATA									
SPFE	PMS	RRB	R12	R24	R48	R72	R96		
0.00	22.00	111.00	122.00	133.00	142.00	0.00	0.00	0.00	0.00

LOSS DATA									
TRP	STRN	ULTRM	HTNL	ERAIN	ERIUR	STRLB	CRSLB	ALSM	HTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	0.00	0.00

UNA1 HYDROGRAPH DATA  
TP= 1.11 CF= .45 NIA= 0 ✓ AS PER CO.E.

RECSSION DATA									
SIMUE	-1.50	SHC12=	-1.00	SHC12=	-0.50	SHC12=	-0.00	SHC12=	-0.50

APPROXIMATE COEFFICIENTS FROM GIVEN STATION CO. AND IP ARE IC=10.88 AND H=16.18 INTERVALS

WATER HYDROGRAPH 92 END-OF-PERIOD ORDINATES, IAGE= 1.12 HOURS, CF= .45 VOL= 1.00									
1.	24.	51.	91.	129.	170.	208.	238.	261.	285.
2.	26.	51.	91.	129.	170.	196.	184.	171.	163.
3.	24.	49.	121.	119.	112.	116.	114.	111.	106.
4.	71.	135.	64.	64.	61.	57.	53.	50.	46.
5.	42.	39.	37.	35.	33.	31.	29.	27.	25.
6.	24.	22.	21.	20.	19.	18.	17.	15.	14.
7.	12.	11.	11.	10.	9.	8.	7.	6.	5.
8.	1.	0.	0.	0.	0.	0.	0.	0.	0.
9.	0.	0.	0.	0.	0.	0.	0.	0.	0.
10.	2.	2.	2.	2.	2.	2.	2.	2.	2.

MAIN	LCFS	LDNS	CUMP	0
51.9	22.60	4.39	110308	
( 635.11 574.31 61.01 ) ( 369.91 )				

**SUBJECT**

## DAM SAFETY INSPECTION

BY DK

BY 205 DATE 3-9-81 PROJ. NO. 80-238-408

CHKD BY DGA DATE 3-10-81 SHEET NO 3 OF 8

SEARCHED BY LLB DATE 3-10-01 SHEET NO. 6 OF 14

The logo for GAI CONSULTANTS. It features the letters 'GAI' in a large, bold, sans-serif font. The letter 'G' is stylized with a horizontal bar across its middle. To the right of 'GAI' is a small square containing the letters 'TS'. Below 'GAI' is the word 'CONSULTANTS' in a smaller, bold, sans-serif font.

## LOCAL INFLOW HYDROGRAPHS, LAKE RENE

PEAK	6 HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
TPS	1043.	787.	138.	2981.
TPS	10.	21.	4.	1105.
INCHES	4.16.	6.19.	6.30	6.40
INCHES	111.11	157.27	160.07	160.02
ACPT	315.	328.	537.	537.
THOUS CU M	461.	651.	663.	663.
PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
TPS	1390.	1010.	355.	2014.
CM6	39.	29.	10.	1473.
INCHES	5.87	8.75	8.40	8.40
INCHES	149.10	209.63	213.37	213.37
ACPT	501.	704.	716.	716.
THOUS CU M	618.	864.	864.	864.
PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
TPS	1738.	1262.	444.	5018.
CM6	49.	36.	13.	1841.
INCHES	7.34	10.32	10.50	10.50
INCHES	186.98	262.09	266.71	266.71
ACPT	626.	880.	896.	896.
THOUS CU M	772.	1086.	1105.	1105.

		PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CF-5	PF-4A	2105.	1514.	521.	211.	78021.
CF-5	CF-5	54.	43.	15.	2209.	
WINDS	WINDS		8.81	12.34	12.60	12.60
MM	MM		221.65	314.51	320.05	320.05
ACT-T	ACT-T		75.1.	105.1.	105.1.	105.1.
THOUS CUB M	THOUS CUB M		9.6.	136.3.	136.6.	1326.
		PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CF-5	CF-5	3475.	2524.	887.	452.	130336.
CF-5	CF-5	98.	71.	25.	13.	3682.
ACT-T	ACT-T		14.64	20.64	21.64	21.00
THOUS	THOUS		312.75	521.18	531.42	533.42
MM	MM		125.2.	176.0.	179.1.	179.1.
ACT-T	ACT-T		154.4.	217.1.	2209.	2209.

## HYDROGRAPH PRINTING

**ROUTE THROUGH LAKE RENT.**

SUBJECT

## DAM SAFETY INSPECTION

## BEAVER POND DAM

BY ZJSDATE 3-9-81PROJ. NO. 80-238-408CHKD. BY DGBDATE 3-10-81SHEET NO. C OF R

LAKE RENE  
OUTFLOW  
HYDROGRAPHS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	745.	60W.	204.	104.	29023.
CMS	21.	17.	6.	3.	844.
INCHES		3.53	4.75	4.82	4.82
MM		89.17	120.77	122.34	122.34
AC-FT		301.	406.	411.	411.
THOUS CU M		312.	500.	507.	507.

0.3PMF

0.4PMF

0.5PMF

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1006.	839.	282.	143.	41055.
CMS	28.	24.	8.	4.	1163.
INCHES		4.08	6.55	6.63	6.63
MM		123.93	168.37	168.41	168.41
AC-FT		416.	558.	565.	565.
THOUS CU M		513.	689.	699.	699.

0.4PMF

0.5PMF

0.6PMF

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1219.	1073.	361.	182.	52549.
CMS	37.	30.	10.	6.	148.
INCHES		6.24	11.14	11.19	11.19
MM		158.52	212.95	215.56	215.56
AC-FT		533.	715.	724.	724.
THOUS CU M		657.	882.	893.	893.

0.4PMF

0.5PMF

0.6PMF

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

MARCEL LAKE INFLOW HYDROGRAPHS									
HYDG	RIUG	TAREA	SNAP	HYDROGRAPH DATA	PRECIP DATA	INPH	INPH1	INPH2	INPH3
1	2.70	0.00	7.00	0.00	0.000	0	0	0	0

\*\*\*\*\*

MARCEL LAKE INFLOW HYDROGRAPHS

HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*


SIH-AREA RUNOFF COMPUTATION

SIH-AREA RUNOFF COMPUTATION									
HYDG	RIUG	TAREA	SNAP	INCON	INCON	INCON	INCON	INCON	INCON
1	2.70	0.00	7.00	0	0	0	0	0	0

\*\*\*\*\*

SUBJECT

DAM SAFETY INSPECTION  
BEAVER POND DAM

BY 2025DATE 3-9-81PROJ. NO. 80-338-408CHKD. BY 260DATE 3-10-81SHEET NO. 7 OF R

Engineers • Geologists • Planners  
Environmental Specialists

LINK#	STATION	ULTIM	WTIM	LOSS DATA	STNS	WTIM	LOSS DATA	STNS	WTIM	LOSS DATA	STNS	WTIM
0	0.00	0.00	1.00	0.00	0.00	1.00	0.00	1.00	0.00	0.00	1.00	0.00

UNIT HYDROGRAPH DATA

TP= 1.75

CP= .45

NTA= 0

APPROXIMATE CLARK COEFFICIENTS FROM  
GIVEN SNYDOR CP AND TP ARE TC=11.0/ AND R=16,600 INTERVALS

UNIT HYDROGRAPH 94 END-OF-PERIOD ORDINATES, LAKE	1.16 HOURS	CP= .45	WUL= 1.00
12. 44. 91. 146. 208. 273. 315. 387.	455.	455.	451.
459. 445. 419. 372. 350. 310. 310. 292.	275.	275.	275.
254. 244. 230. 216. 204. 192. 180. 170.	151.	151.	151.
172. 177. 172. 172. 172. 172. 172. 172.	166.	166.	166.
42. 40. 38. 35. 35. 35. 35. 35.	68.	68.	68.
21. 21. 19. 19. 19. 19. 19. 19.	45.	45.	45.
12. 12. 11. 11. 11. 11. 11. 11.	25.	25.	25.
7. 7. 6. 6. 6. 6. 6. 6.	14.	14.	14.
4. 4. 3. 3. 3. 3. 3. 3.	7.	7.	7.

RAIN EXCS LOSS CUPP Q

SUM 24.49 22.60 2.39 318906.  
( 635.)( 574.)( 61.)( 6198.73)

PEAK 6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS 1734. 1734. 6-HOUR	441. 248.	248.	6552.
CMS 49. 49.	36. 13.	6.	1855.
INCHES 1INCHES	4.37	6.16	6.27
MM 111.02	166.57	159.28	159.28
AC-FT 629.	887.	903.	903.
THOUS CU M 776.	1094.	1113.	1113.

PEAK 6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS 231. 231.	596. 363.	363.	87353.
CMS 65. 65.	48. 17.	9.	2414.
INCHES	5.83	8.22	8.36
MM 148.03	208.10	212.37	212.37
AC-FT	1639.	1183.	1203.
THOUS CU M 1035.	1459.	1484.	1484.

PEAK 6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS 2891. 2891.	745. 379.	379.	102204.
CMS 62. 62.	60. 21.	11.	3092.
INCHES	7.28	10.27	10.45
MM 185.04	260.87	265.46	265.46
AC-FT	1048.	1470.	1504.
THOUS CU M 1923.	1923.	1955.	1955.

LOCAL INFLOW  
HYDROGRAPHS,  
MARCEL LAKE.

SUBJECT

# DAM SAFETY INSPECTION

## BEAVER POND DAM

BY

DJS

DATE

3-9-81

PROJ. NO.

80-238-408

CHKD. BY


DGB

DATE

3-10-81

SHEET NO.

E OF R



	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	569.	253.	894.	455.	131045.
CMS	98.	72.	25.	13.	3711.
INCHES	164.	120.	42.	21.	61484.
MM					17.54
AC-FT					316.55
THOUS CU M	1552.	2148.	1174.	1805.	1805.
					2226.

0.6 PMF

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	5741.	4229.	1491.	758.	216409.
CMS	164.	120.	42.	21.	61484.
INCHES					20.90
MM					PMF
AC-FT					
THOUS CU M	370.	309.	521.	530.	310.92
					3008.
					3711.

PMF

0.6 PMF

### COMBINE HYDROGRAPHS

#### CUBAINE LAKE RENE OUTFLOW HYDROGRAPH WITH MARCEL LAKE INFLOW HYDROGRAPH

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
INCHES	2249.	1810.	652.	331.	95316.
MM	64.	51.	18.	9.	2700.
AC-FT					5.53
THOUS CU M	99.45	3.92.	5.64	5.73	145.53
					1311.
					1620.

0.3 PMF

**SUM OF MARCEL LAKE LOCAL INFLOW HYDROGRAPH AND LAKE RENE OUTFLOW HYDROGRAPH.**

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	3060.	2451.	818.	446.	128418.
CMS	87.	64.	25.	13.	3636.
INCHES					4580.
MM					9.72
AC-FT					146.01
THOUS CU M	109.	101.	141.	134.	1769.
					2182.

0.4 PMF

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
--	------	--------	---------	---------	--------------

CFS	3097.	1106.	562.	562.	161754.
CMS	87.	64.	25.	16.	4580.
INCHES					9.72
MM					246.80
AC-FT					2226.
THOUS CU M	109.	101.	141.	134.	2182.
					2748.

0.5 PMF

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
--	------	--------	---------	---------	--------------

CFS	3133.	106.	52.	52.	193190.
CMS					310295.
INCHES					9353.
MM					19.85
AC-FT					504.15
THOUS CU M	109.	101.	141.	134.	5617.
					5715.

0.6 PMF

### **SUBJE**

DAM SAFETY INSPECTION  
BEAVER POND DAM

84

DATE - 3-9-81 -

PROJ. NO. 60-238-408

CHKD. BY 248

DATE 3-10-81

SHEET NO. *F* OF *R*

**Engineers • Geologists • Planners  
Environmental Specialists**

卷之三

WILHELM WILHELM

卷之三

ROUTE TOTAL HYDROGRAPH THROUGH MARCEL LAKE									
STAGE	FLOW	REC'D	REC'D	TAPE	APLT	JPHT	INAE	INSTAG	1 AUTO
1231.00	0.00	1232.00	1233.00	1234.00	1235.00	1236.00	1236.50	1237.50	1237.50
1232.00	222.00	628.00	1154.00	1776.00	2492.00	2863.00	2863.00	2863.00	2863.00
SUMFACE AREA =	0.	27.	37.	78.					

CAPACITY = 0		ELEVATION = 1215.		ELEVATION = 1231.		ELEVATION = 1240.		ELEVATION = 1260.	
CHNL	SPWID	CHNL	SPWID	CHNL	SPWID	CHNL	SPWID	CHNL	SPWID
1231.0	0.0	1231.0	0.0	1231.0	0.0	1236.5	0.0	1236.5	0.0

TOPEL		DAM DATA		DAVID	
CHNL	SPWID	CHNL	SPWID	CHNL	SPWID
1236.5	0.0	1236.5	0.0	1236.5	0.0


  

PEAK		6-HOUR		24-HOUR		72-HOUR		TOTAL		VOLUME	
CFS	CMS	CFS	CMS	CFS	CMS	CFS	CMS	CFS	CMS	CFS	CMS
2198.	672.	1781.	50.	620.	14.	314.	9.	9052.	2564.	344.	344.
INCHES				3.85		5.36		5.44			
MM				97.87		136.21		136.21		136.21	

MARCEL LAKE  
OUTFLOW  
HYDROGRAPHS



SUBJECT

DAM SAFETY INSPECTION  
BEAVER POND DAMBY DJSDATE 3-9-81PROJ. NO. 80-338-408CHKD. BY DLSDATE 3-10-81SHEET NO. 4 OF RGAI  
CONSULTANTS, INC.  
Engineers • Geologists • Planners  
Environmental Specialists

SUBJECT

## DAM SAFETY INSPECTION

## BEAVER POND DAM

BY DWJDATE 3-9-81PROJ. NO. 80-238-408CHKD. BY DLBDATE 3-10-81SHEET NO. 1 OF 2
 Engineers • Geologists • Planners  
 Environmental Specialists

## \*\*\*\*\* HYDROGRAPH ROUTING \*\*\*\*\*

## ROUTE: TOTAL HYDROGRAPH THROUGH BEAVER DAM RESERVOIR

STAGE MEASUR	CLSS	CLASS	AVG 0:00	NSTP	NSTDL	LAG	AMSK	JPT	INAME	I STAGE 0	I AUT 0
1172.00	1173.00	1174.00	1175.00	0	0	0	0.000	0.000	0.000	0	0
1177.90	1178.00	1178.50	1179.00	0	0	0	0.000	0.000	0.000	0	0
FLOW 6116.00	350.00	1020.00	1970.00	3120.00	3120.00	3120.00	3670.00	4530.00	5150.00	5310.00	5310.00
CAPACITY=	61.	90.	123.	150.	162.	162.	205.	256.	351.		
EL ELEVATION=	116.0	1172.	1174.	1176.	1177.	1177.	1178.	1180.	1182.	1185.	
INEL	172.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
SPWID											
CUOW											
EXPW											
EL.EVL											
CUOL											
CAREA											
FAPU											
DAM DATA											
TUPEL											
CLOUD											
EXPO											
DAWNU											
0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
PEAK	3129.	2976.	1091.	549.	549.	549.	15.	4310.	4310.	4310.	4310.
CFS	CMS	105.	84.	29.	29.	29.	5.62	5.62	5.62	5.62	5.62
INCHES	INCHES		3.95	5.53	5.53	5.53					
MM	MM		100.15	140.55	140.55	140.55	140.71	140.71	140.71	140.71	140.71
AC-PT	AC-PT		1416.	2065.	2065.	2065.	2097.	2097.	2097.	2097.	2097.
THOUS CU M	THOUS CU M		1820.	2547.	2547.	2547.	2586.	2586.	2586.	2586.	2586.
PEAK	5092.	4016.	1403.	1403.	1403.	1403.	712.	712.	712.	712.	712.
CFS	CMS	144.	114.	40.	40.	40.	20.	20.	20.	20.	20.
INCHES	INCHES		5.34	7.46	7.46	7.46	7.57	7.57	7.57	7.57	7.57
MM	MM		135.56	189.08	189.08	189.08	192.36	192.36	192.36	192.36	192.36
AC-PT	AC-PT		1991.	2704.	2704.	2704.	2876.	2876.	2876.	2876.	2876.
THOUS CU M	THOUS CU M		2456.	3431.	3431.	3431.	3486.	3486.	3486.	3486.	3486.
PEAK	6509.	5064.	1768.	1768.	1768.	1768.	897.	897.	897.	897.	897.
CFS	CMS	184.	143.	50.	50.	50.	25.	25.	25.	25.	25.
INCHES	INCHES		6.73	9.40	9.40	9.40	9.54	9.54	9.54	9.54	9.54
MM	MM		170.92	238.75	238.75	238.75	242.35	242.35	242.35	242.35	242.35
AC-PT	AC-PT		2511.	3507.	3507.	3507.	3560.	3560.	3560.	3560.	3560.
THOUS CU M	THOUS CU M		3741.	5221.	5221.	5221.	5301.	5301.	5301.	5301.	5301.
PEAK	6416.	2135.	2135.	2135.	2135.	2135.	1083.	1083.	1083.	1083.	1083.
CFS	CMS	224.	173.	60.	60.	60.	51.	51.	51.	51.	51.
INCHES	INCHES		9.13	11.35	11.35	11.35	11.52	11.52	11.52	11.52	11.52
MM	MM		206.46	286.22	286.22	286.22	292.54	292.54	292.54	292.54	292.54
AC-PT	AC-PT		303.	4334.	4334.	4334.	4398.	4398.	4398.	4398.	4398.
THOUS CU M	THOUS CU M		3047.	4326.	4326.	4326.	4391.	4391.	4391.	4391.	4391.
PEAK	14195.	10465.	3616.	3616.	3616.	3616.	1035.	1035.	1035.	1035.	1035.
CFS	CMS	402.	296.	102.	102.	102.	52.	52.	52.	52.	52.
INCHES	INCHES		13.91	19.22	19.22	19.22	19.50	19.50	19.50	19.50	19.50
MM	MM		153.23	486.20	486.20	486.20	495.39	495.39	495.39	495.39	495.39
AC-PT	AC-PT		5189.	7172.	7172.	7172.	7218.	7218.	7218.	7218.	7218.
THOUS CU M	THOUS CU M		6401.	8846.	8846.	8846.	8917.	8917.	8917.	8917.	8917.

BEAVER POND  
DAM OUTFLOW  
HYDROGRAPHS.
 TOTAL VOLUME  
258473.  
7319.  
9154.  
242.35

 TOTAL VOLUME  
205157.  
5899.  
757.  
192.36

 TOTAL VOLUME  
205157.  
5899.  
757.  
192.36

PMF

0.6PMF


0.5PMF

0.4PMF

SUBJECT

## DAM SAFETY INSPECTION

## BEAVER POND DAM

BY ZTSDATE 7-9-81PROJ. NO. 80-238-408CHKD. BY DLSDATE 3-10-81SHEET NO. J OF R

PEAK FLOW AND STORAGE (AND UP PENDING) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIO	MAXIMUM APPLIED FLOWS				
					1	2	3	4	RATIO
HYDROGRAPH AT RENE	RENE	1.60 ( - 4.14)	1	.30	1043.	1390.	1734.	2085.	.3475.
					39.361( - 29.52)	49.211( - 39.05)	59.051( - 59.05)	68.411(	
ROUTED TO RENE	RENE	1.60 ( - 4.14)	1	.40	725.	1006.	1299.	1596.	.3279.
					20.521( - 20.52)	28.471( - 36.79)	45.191( - 45.19)	92.861(	
HYDROGRAPH AT MARCEL	MARCEL	2.70 ( - 6.99)	1	.30	1734.	2313.	2891.	3469.	.5791.
					49.111( - 49.11)	65.481( - 81.85)	81.851( - 98.22)	163.711(	
2 COMBINED	MARCEL	4.30 ( - 11.14)	1	.40	2249.	3060.	3885.	4712.	.8055.
					63.681( - 63.68)	86.651( - 110.01)	110.011( - 133.43)	250.741(	
ROUTED TO MARCEL	MARCEL	4.30 ( - 11.14)	1	.30	2198.	3031.	3872.	4708.	.8036.
					62.251( - 62.25)	85.821( - 109.63)	109.631( - 133.30)	250.201(	
HYDROGRAPH AT BEAVER	BEAVER	2.70 ( - 6.99)	1	.30	1631.	2174.	2718.	3261.	.5436.
					46.181( - 46.18)	61.571( - 76.96)	76.961( - 92.35)	153.921(	
2 COMBINED	BEAVER	7.00 ( - 18.13)	1	.30	3132.	5101.	6513.	7900.	.14216.
					105.681( - 105.68)	144.621( - 164.44)	164.441( - 223.71)	402.561(	
ROUTED TO BEAVER	BEAVER	7.00 ( - 18.13)	1	.30	3725.	5092.	6509.	7899.	.14195.
					105.491( - 105.49)	141.201( - 184.31)	184.311( - 223.67)	401.951(	

## SUMMARY OF DAM SAFETY ANALYSIS

ELEVATION STORAGE ROUTED	MAXIMUM RESERVOIR PMP	INITIAL VALUE	SPILLWAY CROSS SECTION	TOP OF DAM U., U., U.,	TIME OF OVERTOPPING OVERFLOW HOURS	MAX DURATION OVER TOP HOURS	TIME OF FAILURE OVERFLOW HOURS
LAKE RENE DAM	RATIO OF PMP	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT				
	.30	1762.49	0.00	197.	745.	0.00	43.50
	.40	1763.17	0.00	247.	1076.	0.00	43.50
	.50	1763.70	0.00	292.	1299.	0.00	43.33
	.60	1764.25	0.00	316.	1591.	0.00	43.17
	1.00	1765.36	.36	424.	3279.	3.17	42.00

OVERTOPPING  
ANALYSIS  
SUMMARY:LAKE RENE  
DAM

SUBJECT

## DAM SAFETY INSPECTION

## BEAVER POND DAM

BY DJSDATE 3-9-81PROJ. NO. 80-238-408CHKD. BY DLADATE 3-10-81SHEET NO. K OF REngineers • Geologists • Planners  
Environmental Specialists

ELEVATION STORAGE INITIAL	INITIAL VALUE 1231.00 144.	MAXIMUM DEPTH OVER DAM AC-FT	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF FAILURE HOURS	TOP OF DAM 1236.00 309. 286.3.
							SPILLWAY CHEST
<b>MARCEL LAKE DAM</b>							
.50	1235.60	0.00	279.	2196.	0.00	42.67	0.00
.40	1236.60	.10	312.	3031.	1.33	42.50	0.00
.30	1237.09	.59	326.	3872.	3.13	42.33	0.00
.60	1237.53	1.03	341.	4706.	4.67	42.17	0.00
1.00	1238.65	2.15	362.	6836.	7.13	42.00	0.00
<b>BEAVER POND DAM</b>							
ELEVATION STORAGE INITIAL	INITIAL VALUE 1172.00 61. 0.	MAXIMUM DEPTH OVER DAM AC-FT	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF FAILURE HOURS	TOP OF DAM 1177.40 150. 5150.
.30	1176.44	0.00	132.	3125.	0.00	42.50	0.00
.40	1177.36	0.00	149.	5022.	0.00	42.33	0.00
.50	1178.06	.66	163.	6509.	3.00	42.00	0.00
.60	1178.53	1.13	171.	7899.	6.17	42.00	0.00
1.00	1180.07	2.67	207.	14195.	6.63	41.63	0.00

OVERTOPPING OCCURS @ ≈ 0.40 PMF

SUBJECT

## DAM SAFETY INSPECTION

## BEAVER POND DAM

BY DJSDATE 3-9-81PROJ. NO. 80-338-408CHKD. BY DLBDATE 3-10-81SHEET NO. 6 OF R
 Engineers • Geologists • Planners  
 Environmental Specialists

 (INPUT SAME AS FOR OVERTOPPING ANALYSIS,  
 WITH THE ADDITION OF BREACH CRITERIA  
 GIVEN HERE.)

 BREACHING ANALYSIS  
 (0.43 PMF EVENT)

## DAM SAFETY INSPECTION

## BEAVER DAM 400' BREACHING ANALYSIS \*\*\*\*\*

## 10-MINUTE TIME STEP AND 48-HOUR STORM DURATION

MU	MIN	MIN	1HR	1MIN	WEIR	IPRT	INSTAN
200	0	10	0	0	0	0	0
		JUMP	NET	INPUT	TRACK		
		5	0	0	0		

## MULTI-PLAN ANALYSES TO BE PERFORMED

NPLAN = 6

NHRD = 1

LDTD = 1

RPTD =

.43

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
115	1444	1055.	154.	154.	15915.
115	42.	41.	11.	5.	1583.
INCHES		6.31	6.87	5.03	9.03
MM		160.28	225.40	227.37	229.37
FEET		538.	757.	770.	770.
THOUS CU M		664.	934.	950.	950.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1035.	919.	305.	154.	4487.
CMS	31.	26.	9.	4.	1260.
INCHES		5.29	7.10	7.18	7.18
MM		134.28	180.74	182.49	182.49
AC-FT		451.	605.	613.	613.
THOUS CU M		936.	747.	756.	756.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2486.	1818.	641.	326.	93916.
CMS	70.	51.	18.	9.	2659.
INCHES		6.27	8.83	8.99	8.99
MM		159.13	244.15	288.30	288.30
AC-FT		451.	605.	613.	613.
THOUS CU M		902.	1271.	1294.	1294.
		1112.	1568.	1596.	1596.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	3301.	2644.	946.	481.	13803.
CMS	91.	75.	27.	14.	3919.
INCHES		5.72	8.19	8.32	8.32
MM		145.29	207.94	211.25	211.25
AC-FT		1311.	1876.	1906.	1906.
THOUS CU M		1617.	2315.	2351.	2351.

 MARCEL LAKE  
 LOCAL INFLOW

 MARCEL LAKE  
 TOTAL INFLOW

SUBJECT

## DAM SAFETY INSPECTION

## BEAVER POND DAM

BY DTSDATE 3-9-81PROJ. NO. 80-238-408CHKD. BY DLBDATE 3-10-81SHEET NO. M OF R

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFSS	3287	2610	906	906	132356
CMS	934	74	46	43	3748
INCHES		5.65	7.84	7.85	7.98
MM	14340	149.5	149.5	202.02	202.02
AC-FT	1294	1797	1827	1823	
THOUS CU M		1596	2217	2249	2249

BEAVER POND  
LOCAL INFLOW  
TOTAL INFLOW

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFSS	2317	1759	626	318	91707
CMS	666	50	16	9	2597
INCHES		6.06	8.61	8.78	8.78
MM	153.89	219.11	222.93	222.93	
AC-FT	872	1242	1263	1263	
THOUS CU M		1076	1531	1558	1558

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFSS	5546	4335	1512	778	244063
CMS	157	123	43	22	6345
INCHES		5.76	8.14	8.27	8.27
MM	146.32	206.85	210.08	210.08	
AC-FT	2150	3039	3086	3086	
THOUS CU M		2651	3748	3807	3807

BEAVER POND  
OUTFLOWS:

HYDROGRAPH MINTING  
ROUTE TOTAL HYDROGRAPH THROUGH BEAVER DAM RESERVOIR

	TOPEL	DAM DATA
	1177.4	CLOUD EXPD DAMEDO
		0.0 0.0 0.0

	DAM BREACH DATA
BRWID	Z ELEM TFAIL WSFL FAIL
10.	1.00 1165.00 .50 1172.00 1177.40

STATION BEAVER. PLAN 1; RATIO 1

REGN DAM FAILURE AT 41.67 HOURS  
PEAK OUTFLOW IS 6490. AT TIME 42.17 HOURS

	DAM BREACH DATA
BRWID	Z ELEM TFAIL WSFL FAIL
40.	10.00 1165.00 .50 1172.00 1177.40

STATION BEAVER. PLAN 2; RATIO 1

REGN DAM FAILURE AT 41.67 HOURS

PEAK OUTFLOW IS 8701. AT TIME 42.17 HOURS

BREACH PLAN:

(1)

(2)

SUBJECT

## DAM SAFETY INSPECTION

## BEAVER POND DAM

BY DJS

DATE

3-9-81

PROJ. NO.

80-338-408

CHKD. BY DLB

DATE

3-10-81

SHEET NO.

N OF R



DAM BREACH DATA  
BRWID 2 ELBN TFAIL WSEL FAILED  
10. 1.00 1165.00 3.00 1172.00 1177.40

STATION BEAVER, PLAN 3, RATIO 1

BEGIN DAM FAILURE AT 41.67 HOURS

PEAK OUTFLOW IS 5579, AT TIME 42.20 HOURS

(3)

DAM BREACH DATA  
BRWID 2 ELBN TFAIL WSEL FAILED  
40. 10.00 1165.00 3.00 1172.00 1177.40

STATION BEAVER, PLAN 4, RATIO 1

BEGIN DAM FAILURE AT 41.67 HOURS

PEAK OUTFLOW IS 5761, AT TIME 42.44 HOURS

(4)

DAM BREACH DATA  
BRWID 2 ELBN TFAIL WSEL FAILED  
20. 1.00 1165.00 1.00 1172.00 1177.40

STATION BEAVER, PLAN 5, RATIO 1

BEGIN DAM FAILURE AT 41.67 HOURS

PEAK OUTFLOW IS 6173, AT TIME 42.67 HOURS

(5)

SUBJECT

# DAM SAFETY INSPECTION

## BEAVER POND DAM

BY DDS DATE 3-9-81 PROJ. NO. 80-338-408  
 CHKD. BY PLB DATE 3-10-81 SHEET NO. 0 OF R



THE DAM BREACH HYDROGRAPH WAS DEVELOPED USING A TIME INTERVAL OF .010 HOURS DURING BREACH FORMATION.  
 DOWNSRAME CALCULATIONS USE A TIME INTERVAL OF .101 HOURS.  
 THIS TABLE COMPARES THE HYDROGRAPH FOR DOWNSRAME CALCULATIONS WITH THE COMPUTED BREACH HYDROGRAPH.  
 INTERMEDIATE FLUWS ARE INTERPOLATED FROM END-UP-PERIOD VALUES.



TIME IN HOURS	INTERPOLATED BREACH HYDROGRAPH (CFPS)	COMPUTED BREACH HYDROGRAPH (CFPS)		ACCUMULATED ERROR (CFPS)	ACCUMULATED ERROR (ACC-FT)
		HYDROGRAPH	HYDROGRAPH		
41.667	0.000	5247.	5247.	0.	0.
41.676	.010	5279.	5279.	.47.	.47.
41.686	.020	5304.	5322.	.84.	1.28.
41.696	.029	5382.	5374.	108.	236.
41.706	.039	5361.	5344.	120.	303.
41.716	.049	5359.	5501.	136.	501.
41.725	.059	5316.	5573.	144.	645.
41.735	.069	5396.	5651.	146.	790.
41.745	.079	5644.	5733.	141.	932.
41.755	.088	5953.	5819.	133.	1065.
41.765	.098	6011.	5904.	122.	1187.
41.775	.108	6110.	6002.	107.	1294.
41.784	.118	6188.	6097.	91.	1385.
41.794	.127	6267.	6192.	74.	1460.
41.804	.137	6345.	6289.	56.	1516.
41.814	.147	6423.	6386.	38.	1554.
41.824	.157	6502.	6483.	19.	1572.
41.833	.167	6580.	6580.	0.	1572.
41.843	.176	6664.	6677.	-12.	1537.
41.853	.186	6749.	6772.	-23.	1505.
41.863	.196	6833.	6865.	-32.	1505.
41.873	.206	6912.	6955.	-40.	1465.
41.882	.216	7002.	7054.	-53.	1412.
41.892	.225	7086.	7149.	-66.	1349.
41.902	.235	7170.	7240.	-70.	1279.
41.912	.245	7244.	7329.	-75.	1204.
41.922	.255	7319.	7416.	-71.	1127.
41.931	.265	7421.	7499.	-76.	1051.
41.941	.275	7507.	7579.	-72.	979.
41.951	.284	7591.	7658.	-66.	912.
41.961	.294	7676.	7737.	-62.	851.
41.971	.304	7760.	7814.	-54.	791.
41.980	.314	7844.	7887.	-41.	754.
41.990	.324	7928.	7957.	-26.	725.
42.000	.333	8013.	8013.	0.	725.
42.010	.343	8053.	8066.	-12.	713.
42.020	.353	8094.	8116.	-22.	691.
42.029	.363	8134.	8163.	-29.	661.
42.039	.373	8115.	8208.	-34.	628.
42.049	.382	8215.	8251.	-36.	592.
42.059	.392	8356.	8292.	-36.	556.
42.069	.402	8266.	8333.	-37.	518.
42.078	.412	8337.	8395.	-51.	460.
42.088	.422	8317.	8451.	-70.	316.
42.098	.431	8418.	8504.	-86.	299.
42.108	.441	8529.	8552.	-90.	205.
42.118	.451	8599.	8597.	-99.	107.
42.127	.461	8539.	8638.	-99.	8.
42.137	.471	8519.	8674.	-94.	-87.
42.147	.480	8620.	8683.	-6.	-150.
42.157	.490	8660.	8692.	-17.	-182.
42.167	.500	8700.	8700.	-0.	-112.

PLAN  
②

SUBJECT

## DAM SAFETY INSPECTION

BEAVER POND DAM

BY DJSDATE 3-9-81PROJ. NO. 80-238-408CHKD. BY DJBDATE 3-10-81SHEET NO. P OF R

SUBJECT DAM SAFETY INSPECTION  
BEAVER POND DAM  
BY DJS DATE 7-9-81 PROJ. NO. 80-338-408  
CHKD. BY DLS DATE 3-10-81 SHEET NO. Q OF R



\*\*\*\*\* HYDROGRAPH ROUTING \*\*\*\*\*

ROUTE FROM HEAVEN DAM TO SECTION 17 500 FT D.S. FROM DAM

ISLAND #PK-1	ICOMP 1	ICOMP 0	ISAME 0	ISAME 1	ISAME 0	ISAME 1	ISAME 0	ISAME 1	ISAME 0
All Islands have same ROUTING DATA									

QLOSS	CLOSS	AVG	IRGS	ISAME	ISPT	IPMP	IPMP	LSTR
0.0	0.000	0.00	0	1	0	0	0	0
NSTPS	NSTDY	LAG	AMSK	X	TSK	STRA	ISPRAT	
1	0	0	0.000	0.000	0.000	-1.	0	

NORMAL DEPTH CHANNEL ROUTING

QN(1) QN(2) QN(3) ELNVT VIMAX RLNTH SEL  
.0100 .0350 .0800 1161.0 1180.0 500. .01000


CROSS SECTION COORDINATES STA. ELEV. ETC.  
0.00 1180.00 600.00 1167.00 1104.00 1167.00 1110.00 1161.00 1125.00 1161.00  
1128.00 1164.00 1230.00 1172.00 1130.00 1180.00

STORAGE	0.00	18	.39	.62	.94	1.42	2.05	6.68
	25.69	33.73	42.62	52.37	62.96	74.40	86.69	99.83
OUTFLOW	0.00	63.37	201.78	400.48	680.81	1019.80	1524.80	2843.40
	12732.99	18008.32	24355.47	31026.96	40479.10	50310.71	61556.64	8164.88
STAGE	161.00	1162.00	1163.00	1164.00	1165.00	1166.00	1167.00	1169.00
	1171.00	1172.00	1173.00	1174.00	1175.00	1176.00	1177.00	1179.00
FLUX	0.00	63.37	201.78	400.48	680.81	1019.80	1524.80	2843.40
	12732.99	18008.32	24355.47	31026.96	40479.10	50310.71	61556.64	8164.88

SUBJECT

## DAM SAFETY INSPECTION

BEAVER POND DAM

BY DJSDATE 3-9-81PROJ. NO. 80-338-408CHKD. BY DLBDATE 3-10-81SHEET NO. R OF REngineers • Geologists • Planners  
Environmental Specialists

## SUMMARY OF DAM SAFETY ANALYSIS

		INITIAL VALUE	SPILLWAY CHEST	TOP OF DAM	LAKE RENE DAM	
ELEVATION	1260.0	1260.00	0.	1265.00	395.	
STORAGE OUTFLOW	0.	0.	0.	0.	2029.	
RATIO OF RESERVOIR DEPTH W.S.F.ELEV OUTFLOW	.43	1261.30	0.00	261.	1095.	0.00
INITIAL VALUE	1231.00	1231.00	0.	1236.50	309.	
ELEVATION	1231.00	144.	0.	144.	2863.	
STORAGE OUTFLOW	0.	0.	0.	0.	0.	
RATIO OF RESERVOIR DEPTH W.S.F.ELEV OUTFLOW	.43	1236.74	.24	317.	3267.	2.33
INITIAL VALUE	1172.00	61.	0.	1172.00	61.	
ELEVATION	1172.00	61.	0.	1172.00	61.	
STORAGE OUTFLOW	0.	0.	0.	0.	0.	
RATIO OF RESERVOIR DEPTH W.S.F.ELEV OUTFLOW	.43	1177.50	.10	152.	6490.	.42
INITIAL VALUE	1177.50	.08	0.	151.	8701.	.21
ELEVATION	1177.50	.08	0.	151.	8701.	.21
STORAGE OUTFLOW	0.	0.	0.	0.	0.	
RATIO OF RESERVOIR DEPTH W.S.F.ELEV OUTFLOW	.43	1177.50	.10	152.	6490.	.42

MARCEL LAKE  
DAM

		INITIAL VALUE	SPILLWAY CHEST	TOP OF DAM	MARCEL LAKE DAM	
ELEVATION	1231.00	1231.00	0.	1236.50	309.	
STORAGE OUTFLOW	0.	0.	0.	0.	2863.	
RATIO OF RESERVOIR DEPTH W.S.F.ELEV OUTFLOW	.43	1236.74	.24	317.	3267.	2.33
INITIAL VALUE	1172.00	61.	0.	1172.00	61.	
ELEVATION	1172.00	61.	0.	1172.00	61.	
STORAGE OUTFLOW	0.	0.	0.	0.	0.	
RATIO OF RESERVOIR DEPTH W.S.F.ELEV OUTFLOW	.43	1177.50	.10	152.	6490.	.42

BEAVER  
POND  
DAM

		INITIAL VALUE	SPILLWAY CHEST	TOP OF DAM	BEAVER POND DAM	
ELEVATION	1231.00	1231.00	0.	1236.50	309.	
STORAGE OUTFLOW	0.	0.	0.	0.	2863.	
RATIO OF RESERVOIR DEPTH W.S.F.ELEV OUTFLOW	.43	1236.74	.24	317.	3267.	2.33
INITIAL VALUE	1172.00	61.	0.	1172.00	61.	
ELEVATION	1172.00	61.	0.	1172.00	61.	
STORAGE OUTFLOW	0.	0.	0.	0.	0.	
RATIO OF RESERVOIR DEPTH W.S.F.ELEV OUTFLOW	.43	1177.50	.10	152.	6490.	.42

BREACH  
PLAN

PLAN	RATIO	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	TIME OVER TUP HOURS	TIME MAX OUTFLOW HOURS	TIME FAILURE HOURS
①	.43	8433.	1169.4	42.17	42.17	41.67
②	.43	8645.	1170.0	42.17	42.17	41.67
③	.43	5519.	1169.4	42.33	42.33	41.67
④	.43	5761.	.67	42.44	42.44	41.67
⑤	.43	6173.	.50	42.67	42.67	41.67

## NON-BREACH

PLAN

MAXIMUM  
STAGE, FTTIME  
HOURSMAXIMUM  
FLOW, CFSTIME  
HOURSMAXIMUM  
STAGE, FTTIME  
HOURS

#### LIST OF REFERENCES

1. "Recommended Guidelines for Safety Inspection of Dams," prepared by Department of the Army, Office of the Chief of Engineers, Washington, D. C. (Appendix D).
2. "Unit Hydrograph Concepts and Calculations," by the U. S. Army, Corps of Engineers, Baltimore District (L-519).
3. "Seasonal Variation of Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1,000 Square Miles and Durations of 6, 12, 24, and 48 Hours," Hydrometeorological Report No. 33, prepared by J. T. Reidel, J. F. Appleby and R. W. Schloemer, Hydrologic Service Division, Hydrometeorological Section, U. S. Army, Corps of Engineers, Washington, D. C., April 1956.
4. Design of Small Dams, U. S. Department of the Interior, Bureau of Reclamation, Washington, D. C., 1973.
5. Handbook of Hydraulics, H. W. King, and E. F. Brater, McGraw-Hill, Inc., New York, 1963.
6. Standard Handbook for Civil Engineers, F. S. Merritt, McGraw-Hill, Inc., New York, 1963.
7. Open-Channel Hydraulics, V. T. Chow, McGraw-Hill, Inc., New York, 1959.
8. Weir Experiments, Coefficients, and Formulas, R. E. Horton, Water Supply and Irrigation Paper No. 200, Department of the Interior, United States Geological Survey, Washington, D. C., 1907.
9. "Probable Maximum Precipitation, Susquehanna River Drainage Above Harrisburg, Pennsylvania," Hydrometeorological Report No. 40, prepared by H. V. Goodyear and J. T. Riedel, Hydrometeorological Branch Office of Hydrology, U. S. Weather Bureau, U. S. Department of Commerce, Washington, D. C., May, 1965.
10. Flood Hydrograph Package (HEC- 1) Dam Safety Version, Hydrologic Engineering Center, U. S. Army, Corps of Engineers, Davis, California, July 1978.
11. "Simulation of Flow Through Broad Crest Navigation Dams with Radial Gates," R. W. Schmitt, U. S. Army, Corps of Engineers, Pittsburgh District.
12. "Hydraulics of Bridge Waterways," BPR, 1970, Discharge Coefficient Based on Criteria for Embankment Shaped Weirs, Figure 24, page 46.

13. Applied Hydraulics in Engineering, H. M. Morris and J. N. Wiggert, Virginia Polytechnic Institute and State University, 2nd Edition, The Ronald Press Company, New York, 1972.
14. Standard Mathematical Tables, 21st Edition, The Chemical Rubber Company, 1973, page 15.
15. Engineering Field Manual, U. S. Department of Agriculture, Soil Conservation Service, 2nd Edition, Washington, D. C., 1969.
16. Water Resources Engineering, R. K. Linsley and J. B. Franzini, McGraw-Hill, Inc., New York, 1972.
17. Engineering for Dams, Volume 2, W. P. Creager, J. D. Justin, J. Hinds, John Wiley & Sons, Inc., New York, 1964.
18. Roughness Characteristics of Natural Channels, H. H. Barnes, Jr., Geological Survey Water-Supply Paper 1849, Department of the Interior, United States Geological Survey, Arlington, Virginia, 1967.
19. "Hydraulic Charts for the Selection of Highway Culverts," Hydraulic Engineering Circular No. 5, Bureau of Public Roads, Washington, D. C., 1965.

APPENDIX E

FIGURES

## LIST OF FIGURES

<u>Figure</u>	<u>Description/Title</u>
1	Regional Vicinity and Watershed Boundary Map
2	General Plan and Profile
3	Details of Proposed Repairs

LAKE MASKENOZHA, PA. N.J.  
NW 4 DINGMANS FERRY 15 QUADRANGLE  
N4107.5 W7447.5

1954  
AMS 6068 III NW. SERIES V831







FIGURE 1  
REGIONAL VICINITY  
AND  
WATERSHED BOUNDARY MAP









AD-A099 089

GAI CONSULTANTS INC MONROEVILLE PA  
NATIONAL DAM INSPECTION PROGRAM, BEAVER POND DAM (NDI I.D. NUMB--ETC(U)  
MAR 81 B M MIHALCIN


F/G 13/13'  
DACP31-81-C-0015  
NL

UNCLASSIFIED

C-12  
2  
ACM/2000



END  
DATE  
15 81  
OTIC



Ca. 5' 6" x 10' 6" x 6'  
Produced Because to Existing Day At  
+ CAN'T MAKE NO BETTER +  
DELAWARE TWO, P. O. CONN.  
October 28, 1953



**CONSULTANTS, INC.**  
**FIGURE 3**

**APPENDIX F**

**GEOLOGY**

## Geology

Beaver Pond Dam is located in the glaciated Low Plateaus section of the Appalachian Plateaus physiographic province of eastern Pennsylvania. In this area, the Appalachian Plateaus province is characterized topographically by flat-topped, hummocky hills formed as a result of glaciation and subsequent stream dissection of nearly flat-lying strata. The Devonian age sedimentary rock strata in Pike County regionally strike  $N35^{\circ}E$  and dip gently to the northwest. The Delaware River is the major drainage basin in the area. Major tributary streams intersect the Delaware River at right angles; whereas, smaller streams display a slightly more random tributary pattern. Both major and minor tributary stream systems are joint controlled and exhibit modified rectangular and trellis-type drainage patterns.


Structurally, the area containing Pike County lies on the south flank of a broad, asymmetrical synclinorium that plunges to the southwest. Superimposed on this broad structural basin are numerous anticlinal and synclinal folds characterized by planar limbs and narrow hinges. Due to prior glaciation, low relief and surficial soil cover, fold axes are difficult to trace.

The sedimentary rock sequences in the vicinity of the dam and reservoir are probably members of the Susquehanna Group of Upper Devonian age (see Geology Map). The sedimentological changes observed in the Catskill Formation indicate that the rate of sedimentation exceeded the rate of basin subsidence resulting in a facies change from marine to non-marine strata. On the accompanying geology map the delineation between the Middle and Upper Devonian age sedimentary rock sequences represents the Allegheny Front which separates the Valley and Ridge physiographic province from the Appalachian Plateaus physiographic province.

Approximately half of Pike County, including the dam site, is covered by a blanket of Wisconsin age (most recent) glacial drift which, based on the degree of weathering, was probably deposited during the Woodfordian stage. Valley bottoms are typically covered by recent alluvium and Woodfordian outwash of variable thickness, but typically less than 10 feet. These deposits are characteristically unconsolidated stratified sand and gravel usually with more gravel than sand and some small boulders. The direction of the Wisconsin ice advance, was from the northeast over the Catskill Mountains and from the north over the Appalachian Plateau. The terminal moraine resulting from the southern most advance of the Wisconsin ice sheet in this area is located in the southern portion of Monroe County which borders Pike County to the South.

References:

1. Fletcher, F. W., Woodrow, D. L., "Geology and Economic Resources of the Pennsylvania Portion of the Milford and Port Jervis 15 minute U.S.G.S. Topographic Quadrangles," Pennsylvania Geological Survey, Fourth Series, Harrisburg, Atlas 223, 1970.
2. Sevon, W. D., Berg, T. M., "Geology and Mineral Resources of the Skytop Quadrangle, Monroe and Pike Counties, Pennsylvania", Pennsylvania Geological Survey, Fourth Series, Harrisburg, Atlas 214A., 1978.
3. Sevon, W., Personal Communication, Commonwealth of Pennsylvania Department of Environmental Resources, Harrisburg, December 3, 1980.



NOTE: THE BEDROCK SURFACE IS COVERED WITH PLEISTOCENE AGE WISCONSIN TILL COMPOSED OF SANDS, GRAVELS AND SILTY CLAYS OF VARIABLE THICKNESS

REVISION 12-17-60

**LEGEND**

### UPPER DEVONIAN

**Catskill Formation - Shohola Member** interbedded 5- to 25-foot thick units of greenish-gray and grayish-red very fine to medium-grained sandstone and sandy shale and lesser medium-gray to medium-brown-gray sandstone and shale. Sandstones are predominantly low-rank graywackes. Beds are thin to very thick and may have simple or planar sets of small- to medium-scale, generally low-angle cross stratification. Contacts with shale units are abruptly disconformable to gradational. Sandstones are poorly cemented. Shale is thinly laminated and well cemented. Mud cracks, convolute bedding, and sole marks are present near contacts with sandstone units. Member is more than 2,000 feet thick. Lower contact is gradational and is placed at top of highest red bed of the underlying Anadomink. Anadomink Red Shale Member, medium-grayish red, silty, massive, finely laminated well-cemented shale containing thin beds of brownish-gray sandy siltstone and silty very fine grained sandstone. This is the "first red" going up section in Upper Devonian sequence. Member is about 100 feet thick. Lower contact is gradational and is placed at the base of lowest red bed Delaware River Flage Member, grayish-green, massive, laminated sandstone and lesser interbedded sandy shale. Beds range from a few inches to as much as 4 feet thick. Sandstones are low-rank graywackes and contain no marine fossils. Member is about 300 feet thick. Lower contact is gradational.

### MIDDLE DEVONIAN

**Mahantango Formation** - Upper member medium-dark-gray, fairly coarse grained, thin-bedded siltstone and silty shale; member is about 700 feet thick and is separated from lower member by the "Centerfield Reef," a calcareous siltstone biostrome containing abundant horn corals. The Centerfield is about 25 feet thick, lower member, virtually same lithology as upper member. Unit is about 1,100 feet thick. Lower contact is gradational.

**Marcellus Shale** - Dark-gray, evenly laminated, silty clay shale and clayey silt shale. Unit commonly contains very hard lime concretions and is well cleaved; bedding is generally obscured. Member is about 75-feet thick. Lower contact is gradational.

SCALE

## GEOLOGY MAP

## REFERENCES

GEOLOGIC MAP OF NORTHEASTERN PENNSYLVANIA. COMPILED BY  
EDW. W. STOSE AND O. A. JUNGSTEDT COMMONWEALTH OF PENN-  
SYLVANIA DEPT. OF INTERNAL AFFAIRS DATED 1932. SCALE  
1" = 5 MILES.

